

Ice Island Study

Draft Report

MMS Project #468

APPENDIX B

Prepared for:

Minerals Management Service
US Department of the Interior

Prepared by:

C-CORE

C-CORE Report:

R-05-014-241v1.0
August 2005



C-CORE
Captain Robert A Bartlett Building
Morrisey Road
St. John's, NL
Canada A1B 3X5

T: (709) 737-8354
F: (709) 737-4706

info@c-core.ca
www.c-core.ca



Sandwell Engineering Inc.
805, 900 – 6 Avenue SW
Calgary, Alberta, Canada T2P 3K2
Tel: 403 237 8035
Fax: 403 215 6350

Pioneer Natural Resources Ltd.
Anchorage, Alaska, USA
Thetis Ice Island

31 October 2003
242013

Prepared By: _____ **31 October 2003**
D. M. Masterson, Ph.D., P.Eng. Project Manager

Reviewed By: _____ **31 October 2003**
P. A. Spencer, Ph.D., Senior Scientist

NOTICE

This document is for the private information and benefit only of the client for whom it was prepared and for the particular purpose previously advised to Sandwell Engineering Inc. ["Sandwell"]. The contents of this document are not to be relied upon or used, in whole or in part, by or for the benefit of others without prior adaptation and specific written verification by Sandwell.

Particular financial and other projections and analysis contained herein, to the extent they are based upon assumptions concerning future events and circumstances over which Sandwell has no control, are by their nature uncertain and are to be treated accordingly. Sandwell makes no warranties regarding such projections and analysis.

Sandwell and its corporate affiliates and subsidiaries and their respective officers, directors, employees and agents assume no responsibility for reliance upon this document or any of its contents by any party other than Sandwell's client.

Copyright to this document is wholly reserved to Sandwell.

Table of Contents

1	Thetis Ice Island Wells	1-1
1.1	Description of the Project – Overview and Purpose:	1-1
2	DESCRIPTION OF LOCATION	2-1
3	Design	3-1
3.1	Island Design	3-1
3.1.1	Design water depth	3-1
3.1.2	Seabed Mechanical Properties	3-1
3.1.3	Design Ice Thickness	3-1
3.1.4	Design Ice Load	3-2
3.1.5	Spray Ice Material Properties	3-3
3.1.6	Island Geometry	3-4
3.1.7	Ice Island Stability	3-7
3.1.8	Alternate Island Design	3-13
3.1.9	Island Bearing Capacity	3-13
3.1.10	Creep Settlement	3-14
3.1.11	Well Conductor and Cellar	3-14
3.2	QC and Monitoring During Drilling	3-15
3.2.1	Construction QC and Monitoring	3-15
3.2.2	Post Construction Verification	3-15
3.2.3	Monitoring During Drilling	3-16
3.3	Revised Design	3-16
3.3.1	Design Ice Force	3-17
3.4	Access Road	3-19
4	Construction Methods and Transport	4-1
4.1	Spraying	4-1
4.2	Chips and Water Hauling	4-1
4.3	Verification	4-2
5	Construction	5-1
5.1	Ivik Ice Island:	5-1
5.2	Oooguruk Ice Island	5-3
5.3	Natchiq Ice Island:	5-4
5.4	Ivik Ice Road	5-8
5.5	Oooguruk Ice Road:	5-9
5.6	Natchiq Ice Road	5-10
6	Performance	6-1
6.1	Roads	6-1
6.2	Islands	6-1

7	References	7-1
	Appendix A	1
	Appendix A1: All Spray Ice Densities	1
	Appendix A2: Road Ice Density	3
	Appendix A3: Natchiq Ice Island Density Data	5
	Appendix A4: Ivik Ice Island Density Data	9
	Appendix A5: Oooguruk Ice Island Density Data	13
	Appendix B1: Ice Motion Data for Ivik Sea Ice Monument	1
	Appendix B2: Ice Motion Data for Oooguruk Sea Ice Monument	2
	Appendix B3: Ice Motion Data for Natchiq Sea Ice Monument	4
	Appendix C1: Sea Ice Flow Monitoring for Oooguruk	1
	Appendix C2: Sea Ice Flow Monitoring for Ivik Ice Island	3
	Appendix C3: Sea Ice Flow Monitoring for Natchiq	5
	Appendix D1: Ice Pad Stability For Ivik	1
	Ivik Pad Motion 4	1
	Ivik Pad Motion 5	3
	Appendix D2: Ice Pad Stability Survey for Oooguruk	5
	Appendix D3: Ice Pad Stability Survey Natchiq	8
	Appendix E: Selected Photographs	

1 *Thetis Ice Island Wells*

1.1 DESCRIPTION OF THE PROJECT – OVERVIEW AND PURPOSE:

During the winter of 2002/2003 three grounded ice islands were built in the near-shore region between the Kuparuk River Unit and Thetis Island. An exploration well was drilled from each of the three ice islands. To provide access to these ice islands, grounded ice roads were built for the transportation of the drill rigs. The construction of these islands used a combination of seawater spray ice with ice chip application while the roads were constructed using free flooding and also with ice chip application. In both the islands and roads, the ice chip hauling was carried out by tandem trucks.

Sandwell Engineering Inc. was contracted by Pioneer Natural Resources Alaska, Inc. to design the islands and to perform site engineering for the islands and ice roads. The following tasks were performed:

1. The design of the islands and assistance with the permitting required. The design document was part of the submission to the regulatory agency.
2. The project began with the layout of the location of the islands and roads by Lounsbury and Associates. The safety of all personnel involved as well as the best possible routing was thus ensured.
3. Sandwell then advised and helped in the equipment selection for the construction of the ice islands and roads.
4. During construction:
 - a. Sandwell monitored the quality and quantity of the placed material for the ice roads and islands.
 - b. Sandwell advised on correct construction procedures especially spraying the islands.
 - c. Sandwell also aided the surveyors in monitoring the ice movement.
 - d. Sandwell monitored the temperature and the settlement of the islands.
5. Tests were performed to determine the suitability of the roads for moving the rigs.
6. Sandwell verified the density and continuity of the islands prior to drilling. During drilling Sandwell monitored island performances using data collected by themselves and Lounsbury. A stipulation of the permit to use the islands as a drilling support was that pre-verification and island performance during drilling was monitored.

2 DESCRIPTION OF LOCATION

The islands are all located off the Oliktok Point Dock:

1. Ivik Ice Island located at T13 N, R8 E, Section 7 Umiat Meridian.
2. Ooguruk Ice Island located at T13 N, R8 E, Section 31 Umiat Meridian.
3. Natchiq Ice Island located at T13 N, R8 E, Section 16 Umiat Meridian.

The roads connecting these islands to shore all start at Oliktok Dock and continue in a SW direction along the shore for about 3.7 miles, where an ice road branches off from the shore road and heads in a Westerly direction for about 3 miles to the Natchiq Ice Island. The shore road continues in a SW direction for about 4 miles until it reaches the Spurr Road at Kalubik Creek and continues along the shore in a Westerly direction for 2.3 miles where the ice road starts. The ice road then runs in a NW direction for about 4.3 miles, then in a NE direction for 2.3 miles where the ice road reaches Ivik Ice Island. The ice road continues North for 1.7 miles where it reaches Ooguruk Ice Island. Figure 2-1, below, shows a map of the wellsites and the roads leading to the islands.

THETIS PROJECT
ICE PADS AS-BUILT
AS-BUILT INFORMATION OBTAINED BY HANDHELD GPS SURVEY



ICE PADS	SQUARE FEET	ACRES
Ⓐ Storage Pad	52,165	1.20
Ⓑ Storage Pad	88,858	2.04
Ⓒ Ice Chipping Area	424,737	9.75
Ⓓ Ice Chipping Area	6,913,595	158.71
Ⓔ Ice Chipping Area	18,022,635	413.74
Ⓕ Storage Pad	2,662,452	61.12
Ⓖ Storage Pad	67,062	1.54
Ⓗ Ice Chipping Area	771,102	17.70
Grand Total:	20,002,606	686.81

THETIS PROJECT
ICE ROAD AS-BUILT MAIN ROADS
AS-BUILT INFORMATION OBTAINED BY HANDHELD GPS SURVEY

SEGMENT	Lineal Feet	Mileage
B.O.P. to PI N-4	19,070'	3.61
PI N-4 to Oooguruk 1	78,061'	14.78
PI N-4 to Natchiq 1	16,141'	3.06
PI HH-27 to Water Source A & B	13,852'	2.62
Spur Road at Kaluk Creek	1,494	0.29
Grand Total:	128,618	24.36

WATER SOURCE LOCATIONS
COORDINATES ARE NAD 27

	Latitude	Longitude
A	70° 29' 59.0"	150° 22' 38.4"
B	70° 30' 01.0"	150° 22' 34.6"
C	70° 25' 57.8"	150° 06' 17.5"
D	70° 26' 01.5"	150° 06' 06.3"



3 Design

3.1 ISLAND DESIGN

3.1.1 Design water depth

According to chart datum, the sites have the following water depths.

Location	Chart Depth	Design Depth
Natchiq	7.5 ft.	9.5 ft.
Ivik	10 ft.	12 ft.
Ooguruk	12 ft.	14 ft.

Table 3-1 Design Water Depths

The above chart elevations have been taken as Mean Low Low Water (MLLW). Previous analysis of water level measurements obtained by NOAA from the Sea Water Treatment Plant (STP) at Westdock indicate that a 1 in 5 year storm surge during the January to April time frame would raise the water level 2 ft. above the chart levels.. Thus the design water depth for calculating island stability is 2.0 ft greater than the chart water depth.

3.1.2 Seabed Mechanical Properties

The seabed is alluvial and consists of silts and sand, possibly with some organics. It is represented as a frictional material with an internal friction angle (ϕ) of 33 degrees and zero cohesion. Thus the shear strength of the seabed material is given by:

$$\tau = \sigma N \tan(\phi) \quad \text{Equation 3-1}$$

Where: σN = normal stress

The larger the normal stress, the more shear strength the seabed material will supply for resisting ice loads. It will be shown that the normal stress is supplied by the weight on bottom (WOB) of the ice island.

3.1.3 Design Ice Thickness

The natural sea ice grows throughout the winter and reaches a maximum thickness in spring. Because of the sheltered location only first-year ice will be encountered in the region of the ice island. Thicker, multi-year ice does not intrude these shallow, regions sheltered by the presence of the further offshore Barrier Islands. For the western North Slope area of Alaska, the mean plus one standard deviation ice thickness is given by the following linear regression formulae:

$$h = 29.37 + 0.349 D \text{ (inches)} \quad \text{Equation 3-2}$$

Where: D is the number of days from December 1. An ice thickness of 78" (6.5 ft.) is reached on or about April 20. While drilling must be finished by March 31, other operations such as well testing could be continued past this date, and 6.5 ft. is normally considered the appropriate design thickness.

By early January of 2003, it was known that the average ice thickness at the sites was 2.25 ft. According to the accepted equations the mean ice thickness should have been 3.1 ft. The early winter in 2002 was significantly warmer than normal. Since there was actual information on the ice thickness, an adjustment to the projected maximum design thickness was possible. Using Jan 1 as the starting time, there are 110 days to April 20 and the adjusted design ice thickness is 5.7 ft rather than 6.5 ft

3.1.4 Design Ice Load

The design ice load/ft of the ice island at the end of the winter season was determined by multiplying the design thickness of 5.7 ft times the ice pressure. The effective ice pressure is based on "Joint Industry Project Beaufort and Chukchi Sea Arctic Production Platforms - Update", report by Sandwell, 1991, and presented in Masterson and Spencer, 2000. Figure 3-1 contains this ice pressure vs. thickness curve that allows one to calculate the global ice load on wide structures. For the design ice thickness at the present sites, the global ice pressure is 200 psi. The data were generally obtained from crushing on vertically sided structures. The ice sheet will likely fail in flexure at the island boundary at pressures less than the crushing pressure. The value of 200 psi is above the envelope containing the highest recorded ice pressure and thus represents a conservative ice strength value.

The data used in Figure 3-1 is current and contains information collected during ice interaction from several full scale structures, especially Gulf's Molikpaq, the Hans Island tests, etc., located in the Beaufort Sea and other heavy, active ice areas. Thus the load obtained is based on all available, full-scale data and on ice interactions outside the creep range.

Thus the global ice load at the end of the season (April 20 of 2003) is calculated as:

$$F_i = p \times W_{eff} \times h_n \quad \text{Equation 3-3}$$

Where:

- F_i = global ice load
- W_{eff} = island effective width at water line
- h_n = design ice thickness = 5.7 ft
- p = global ice pressure = 200 psi
= 28,800 psf




Figure 3-1 Global Ice Crushing Pressure vs. Ice Thickness

3.1.5 Spray Ice Material Properties

Spray Ice Material Properties Below the Waterline

In determining the sliding resistance of spray ice islands, the shear strength of the spray ice itself must also be considered since, depending on the bottom soil conditions, a shear failure could develop on a plane through the island itself.


There is limited data on the shear strength of spray ice below waterline. Available data sources are the Sohio Test Ice Island, (Geotech / Golder, 1985, Goff and Masterson, 1986) and the Panarctic Spray Ice Platforms (Masterson et al, 1987),  Table 4-6. The following bounds on the shear strength C of saturated spray ice are indicated by various test methods are summarized in Table 3.2:

Table 3-2 Underwater Spray Ice Strength

Pressure meter data	14 psi (99 kPa) < C < 21 psi (145 kPa)
Borehole jack tests	21 psi (147 kPa) < C < 31 psi (217 kPa)
Flat jack tests	8 psi (55 kPa) < C < 11 psi (77 kPa)
Cone penetrometer tests	5.7 psi (40 kPa) < C < 7 psi (50 kPa)

The available data suggests that the spray ice below water line is also a plastic, low friction material. The shear strength of spray ice below the waterline was conservatively taken as the lowest recorded strength and a shear strength of 5.7 psi (40 kPa) was chosen for designs in the 1980s.

An extensive series of cone penetrometer tests was conducted at the Karluk Island during the verification program (I.C.E., 1989, Bugno et al, 1990). The average bearing pressure below the waterline was 39.5 tsf (3.8 MPa). The range was:

$$16.7 \text{ tsf (1.6 MPa)} < \text{Bearing Capacity} < 64.7 \text{ tsf (6.3 MPa)}$$

Assuming, as is standard practice, (Terzaghi et al, 1996) that the shear strength is 1/6 of this, then the Karluk Island had the following bounds on shear strength below waterline.

$$38 \text{ psi (267 kPa)} < C < 150 \text{ psi (1,050 kPa)}$$

The lack of voids and general continuity of the ice at Karluk, plus the high cone test results indicate a high shear strength. A weighted mean shear strength using all of the above data is 8.2 psi. The range in the shear strength was used to estimate the weight of the data value.

The spray ice has considerably higher shear resistance than the sand of the seabed. Considering the shear strength of 8.2 psi, an ice island with a core radius of 300 ft would have an internal shear resistance of $\pi \times 3002 \times 8.2 \times 144 = 334,000$ kips. The next section will demonstrate that shear failure through the sea bottom material governs in the sliding stability calculation.

Spray Ice Properties Above the Waterline

Data from spray ice platforms and islands suggests that the spray ice behaves as a Mohr-Coulomb material such that the shear strength, τ is given by (Geotech, 1988, Fig. 2.4.1):

$$\tau = C + N \tan \phi \qquad \text{Equation 3-4}$$

Where:

$$C = 41 \text{ psi}$$

$$\phi = 0.85^\circ$$

$$N = \text{normal pressure (psi)}$$

The above water material has a cohesion of 41 psi as compared with 8.2 psi for the underwater material. Thus the shear resistance through a plane in the above water section of the ice would be at least 1.67×10^6 kips.

3.1.6 Island Geometry

Having established the seabed, pack ice and spray ice strength parameters required, it is now possible to determine the island geometry required to support the drilling operation and to resist the lateral loads. The idealized island geometry for the islands is given in Figure 3-2. The grounded portion of the island forms the core of the island while beyond there is the sacrificial edge which, in the event of a major ice movement, would be subject to shear type failure.

All critical, non-relocatable facilities, such as the drilling rig and any camp, must be located within the core radius.

The shape of the ice island edge is very different from that of gravel or other earth. Since, unlike soil or gravel, the ice is buoyant, and since the natural ice sheet is bent and submerged during spraying of the island, the under water part of the edge naturally takes on the reverse taper shown. Profiles taken with drills after the completion of construction have generally confirmed this shape of the island edge.

The lateral ice force is calculated as previously described, where the island width is that of the core plus the taper running out to the natural ice. The taper can run further than shown in Figure 3-2, due mainly to overspray. This overspray can be removed during construction and placed on the island proper. Also, the edge geometry, altered by overspray, will result in a lower ice force, as will be shown.




Figure 3-2a Geometry of Natchiq Ice Island




Figure 3-2c Geometry of Oooguruk Ice Island

3.1.7 Ice Island Stability

Core Resistance of the Island to Sliding

The equation describing the resistance to the island sliding on the seabed from forces due to moving ice is given by:

$$\text{Resistance} = \frac{\pi D_c^2}{4} [c + \{\gamma_i h + (\gamma_{si} - \gamma_w) H\} \tan(\phi)]$$

Equation 3-5

Where:

- D_c = core diameter (ft.)
- γ_i = above water spray ice density
= 40 lb/ft³
- γ_{si} = below water spray ice density
= 57.8 lb/ft³
- γ_w = sea water density

- $\gamma = 64 \text{ lb/ft}^3$
- h = island freeboard (ft.)
- H = water depth (ft.)
- ϕ = bottom material friction angle
= 33°
- c = bottom material cohesion
= 0

Passive Edge Failure and Ridge Building

Ice island interaction fringe geometry and failure mechanisms limit the development of horizontal ice forces in the structure, despite an infinite source of driving force. This is schematically presented in Figure 3-3. During an event, the ice force builds up until the island fringe possibly fails upwards or downwards. This is illustrated in Figure 3-3. Edge failure causes the least distress to the island and will not result in the loss of a well, in contrast to overall sliding. As a result, design of the edge taper was a key consideration for the Karluk ice island (Geotech, 1988).

Once passive edge failure is initiated a nominal vertical force due to eccentricities will initiate flexural failure of the ice sheet. Once this flexural failure is initiated the ridge building failure mechanism will become the dominant failure mechanism and will dictate the magnitude of horizontal force that will be developed in the structure. Parmerter and Coon (1972) have developed a model which allows the prediction of mean and maximum rubble building force. The limiting maximum horizontal breakout load in this model will be dictated by the island passive edge failure.




Figure 3-3 Edge Failures

Sandwell

While edge failure can limit the ice force on the island, the more conservative approach of calculating equilibrium, and thus the required island geometry, based on rigid body sliding has been used. The results of the stability calculations are listed in Table 3-3a, Table 3-3b and Table 3-3c for the three ice islands.



Table 3-3a Natchiq Stability and Geometry Calculation Results

initice	3	ft.	Initial ice thickness
depth	9.5	ft.	Water depth
h	5.7	ft.	Spring ice pack thickness
bwtaper	44	ft.	Below water taper width
p	200	psi	Design ice pressure
awden	38	lb/ft ³	Above water ice density
bwden	57.8	lb/ft ³	Below water density
swden	64	lb/ft ³	Sea water density
cohesion	0	psf	Soil cohesion
phi	33	deg	Soil internal friction angle

Island Core Radius	Island Freeboard	Effective Width	Above Water Taper Width	Ice Force	Sea Water Density	Above Water Ice Density	Below Water Ice Density	Vol Above Water	Vol Below Water	Wt on Bottom	Bottom Contact Area	Sliding Resistance	Factor of Safety	Volume Spray Ice
radius (ft)	fboard (ft)	width (ft)	awtaper (ft)	force (kips)	swden (lb/ft ³)	abwden (lb/ft ³)	bwden (lb/ft ³)	awvol (ft ³)	bwvol (ft ³)	wob (kips)	area (ft ²)	resist (kips)		sprayvol (ft ³)
200	29.3	517	58.6	84,915	64	38	57.8	4,869,862	1,374,919	176,530	144,728	114,640	1.35	6,066,173
250	24.0	596	47.9	97,816	64	38	57.8	5,665,194	1,924,415	203,346	202,570	132,054	1.35	7,330,301
300	20.3	681	40.6	111,815	64	38	57.8	6,545,238	2,624,914	232,445	276,307	150,951	1.35	8,815,145
350	17.7	771	35.4	126,531	64	38	57.8	7,521,412	3,673,730	263,037	366,142	170,818	1.35	10,729,434



Table 3-3b Ivik Stability and Geometry Calculation Results

initice	3	ft.	Initial ice thickness
depth	12	ft.	Water depth
h	5.7	ft.	Spring ice pack thickness
bwtaper	44	ft.	Below water taper width
p	200	psi	Design ice pressure
awden	38	lb/ft ³	Above water ice density
bwden	57.8	lb/ft ³	Below water density
swden	64	lb/ft ³	Sea water density
cohesion	0	psf	Soil cohesion
phi	33	deg	Soil internal friction angle

Island Core Radius (ft)	Island Freeboard (ft)	Effective Width (ft)	Above Water Taper Width (ft)	Ice Force (kips)	Sea Water Density (lb/ft ³)	Above Water Ice Density (lb/ft ³)	Below Water Ice Density (lb/ft ³)	Vol Above Water (ft ³)	Vol Below Water (ft ³)	Wt on Bottom (kips)	Bottom Contact Area (ft ²)	Sliding Resistance (kips)	Factor of Safety	Volume Spray Ice (ft ³)
200	29.7	519	59.3	85,144	64	38	57.8	4,943,196	1,748,022	177,004	145,669	114,948	1.35	6,512,610
250	24.3	597	48.6	98,045	64	38	57.8	5,762,501	2,444,189	203,821	203,682	132,363	1.35	7,947,382
300	20.6	683	41.3	112,044	64	38	57.8	6,673,065	3,331,356	232,922	277,613	151,261	1.35	9,649,413
350	18.1	772	36.2	126,792	64	38	57.8	7,707,618	4,727,448	263,579	367,852	171,170	1.35	11,969,358



Table 3-3c Oooguruk Stability and Geometry Calculation Results

initice	3	ft.	Initial ice thickness
depth	14	ft.	Water depth
h	5.7	ft.	Spring ice pack thickness
bwtaper	44	ft.	Below water taper width
p	200	psi	Design ice pressure
awden	38	lb/ft ³	Above water ice density
bwden	57.8	lb/ft ³	Below water density
swden	64	lb/ft ³	Sea water density
cohesion	0	psf	Soil cohesion
phi	33	deg	Soil internal friction angle

Island Core Radius radius (ft)	Island Freeboard fboard (ft)	Effective Width width (ft)	Above Water Taper Width awtaper (ft)	Ice Force force (kips)	Sea Water Density swden (lb/ft ³)	Above Water Ice Density abwden (lb/ft ³)	Below Water Ice Density bwden (lb/ft ³)	Vol Above Water awvol (ft ³)	Vol Below Water bwvol (ft ³)	Wt on Bottom wob (kips)	Bottom Contact Area area (ft ²)	Sliding Resistance resist (kips)	Factor of Safety	Volume Spray Ice sprayvol (ft ³)
200	29.9	520	59.9	85,328	64	38	57.8	5,002,501	2,049,983	177,385	146,427	115,195	1.35	6,873,876
250	24.6	598	49.2	98,228	64	38	57.8	5,841,047	2,864,103	204,202	204,579	132,611	1.35	8,445,842
300	20.9	684	41.8	112,229	64	38	57.8	6,776,146	3,901,306	233,305	278,665	151,510	1.35	10,322,444
350	18.4	774	36.8	127,008	64	38	57.8	7,861,346	5,597,625	264,026	369,262	171,460	1.35	12,993,263

3.1.8 Alternate Island Design

The above island design is predicated upon a design ice thickness of 5.7 ft. for the lateral ice force calculation. Should the resulting 20 ft. freeboard not be achievable within a reasonable time frame to drill the well, a mitigating approach is planned. While there will be ice motion during the winter even in these sheltered locations, it is not probable that it will be greater than 20 ft. The short duration of the well will only allow at most for one such sudden movement. To mitigate its effects, the natural ice cover will be reduced in thickness completely around the island at a radius of 400 ft. or greater. An ice chipper, common on the North Slope of Alaska for building tundra ice roads and ice pads, will be used to reduce the thickness of the natural ice to 3.7 ft. over the 20 ft. width on the circumference around the island. By doing this, the island freeboard above water may be reduced to 14 ft. from the design freeboard of 20.6 ft. quoted for the Ivik well. Since Ivik is the first well, it is the one most likely to require the implementation of this measure. The factor of safety against sliding will be maintained at 1.35. Note that this alternate island design relies on there being limited horizontal ice movement and the mitigation method is not generally applicable.

3.1.9 Island Bearing Capacity

Spray ice has proven to be a material very capable of supporting its own load when set down on the seabed and of supporting heavy surface loads such as drilling rigs. This is accomplished by the construction method whereby the sprayed ice is put down with still some unfrozen seawater content and the freezing process is completed on the island surface. By doing this the development of good cohesion in the spray ice material is assured. This is in contrast to materials such as artificial snow which have little cohesion and provide a weak bearing surface.

Below Water Capacity

The observed behavior indicates that spray ice is generally a cohesive material. From foundation theory for a circular plate (Timoshenko, 1996) the bearing capacity is:

$$q = 1.2 cN_c$$

Where:

c = shear strength of the material

$$N_c = 5.14$$

The below water shear strength has previously been stated as 8.2 psi or 1,180 psf. The 8.2 psi is based on all available, reliable data and is lower bound strength. Thus the bearing capacity q of the below water ice is 7,283 psf. Thus the bearing capacity of the below water spray ice exceeds the required capacity by a factor of 8.

Alternatively, Timoshenko gives, for the “undrained” case, the shear strength as:

$$q = 6.2c$$

This leads to approximately the same bearing capacity as above.

Above Water Capacity

Previously, the shear strength of the above water ice was given as 41 psi or 5,900 psf. Using the previous formulations from Timoshenko for bearing capacity, the value for the above water ice will be 36,000 psf.

3.1.10 Creep Settlement

The combination of the rig load plus the weight of the spray ice will cause vertical creep settlement of the heavier loads during drilling of the well. Creep settlements in the order of 8 inches were measured at Karluk in 1989. The short duration of this project's wells will result in less creep settlement. Note that some of the creep settlement of the spray ice material occurs during the construction process and prior to the time when the rig is installed on the island. Simple calculations indicate that the dominant load causing creep is from the weight of the island and the rig ground pressure is small compared to that from the island weight.

3.1.11 Well Conductor and Cellar

Conductor and Ice Melt

To avoid excessive melt of ice around the conductor, and thus undermining of the rig support, it will be necessary to use an insulated conductor for drilling. Use of the standard North Slope gel/diesel filled annulus between the surface casing and the conductor will be sufficient.

Well Cellar

In general, an insulated cellar and cellar floor are required to avoid melting of ice and undermining the rig. This melting can occur in a relatively short time so even short duration wells require the insulated cellar. In addition, there must be insulation at least 6 inches thick placed under the rig mats. Alternatively, insulated rig mats can be used, if they are available.

The cellar could be a standard 12-foot diameter by 8-foot tall corrugated metal pipe (CMP), insulated with six inches of spray-applied polyurethane foam. Eight-inch thick insulated panels can be used under the cellar. The floor of the cellar can be poured using permafrost cement.

The properties of the steel culvert can be as follows:

Wall thickness	= 14 gauge or 0.0747 in.
Section area	= 1.113 in 2/ft
Inertia	= 0.1306 in 4/ft
Section Modulus	= 0.2431 in 3/ft.
Radius of gyration -r	= 0.3427 in.

The conductor and well cellar thermal requirements and cellar mechanical properties will require further investigation once the rig requirements are known.

3.2 QC AND MONITORING DURING DRILLING

The previous sections have determined the design parameters and geometry of the island required to provide assurance that it will provide a safe and stable drilling platform. Essentially, the island must be firmly grounded, with enough freeboard to ensure adequate contact with the seabed to resist the design lateral ice loads. The spray ice formed during construction must have adequate density and volume to provide the required weight which ensures the correct bottom contact at the seabed. The spray ice also must have the required minimum shear strength to ensure that the lateral ice loads will not produce a shear displacement through a plane of weakness in the island.

3.2.1 Construction QC and Monitoring

During the construction phase of the island, the QC tasks verify material quantity and material quality as required by the design and will consist of ice volume, ice temperature and ice density measurements plus recording of key pump operating parameters. A key activity during the construction consists of visual inspection of the spraying process and of the island itself.

Table 3-4 Construction Phase QC and Monitoring

Item	Number of sites	Frequency
Constructed Volume/Shape	Build-up stakes	Every day
Ice Temperature	1 Vertical profile	Every day
Density/Salinity	1 Core	Every other day
Pump operation parameters	All pumps	Every Day

The ice thickness and the related constructed volume are measured at predetermined locations using 1 inch steel tubing installed in the ice at the start of construction. The proposed locations of the measurement stations are shown in Figure 3-2. The steel tubing will be extended during spraying to ensure they are accessible for measurement. Note after the islands are well grounded, differential GPS of the surface elevation will be used instead of build-up stakes to monitor the progress of the construction. Ice temperature is measured using “strings” of thermistors wired to a continuous cable with a terminal box and switch at the ice surface. Measurements of temperature will be taken at 2 foot intervals.

3.2.2 Post Construction Verification

At the completion of the island construction, a program is conducted to verify that the design conditions for the island have been met or exceeded. The activities associated with this phase are:

- Review of the information on island geometry, density and temperature obtained during construction. A review of the level ice thickness at the site.
- Using a hot water drill, perform spot checks on the island total thickness a select thickness monitoring stations. Approximately 10 percent of the thickness stations would be checked in this manner.

- Cone penetrometer tests (CPTs) can be conducted using a soils rig available on the North Slope if time permits and it is considered necessary. This is an optional activity.

3.2.3 Monitoring During Drilling

Because of the short drilling time anticipated, monitoring during drilling will be kept to a minimum. The principal activities will be the measurement of settlement of the ice surface using standard and/or DGPS surveying techniques, measurement of ice temperature near the cellar and conductor using thermistor strings and adjacent level ice sheet movement monitoring.

The horizontal position of the island, measured at a pre-determined point on the island, will be established twice daily. Also, any movement of the surrounding ice relative to the island will be determined at an established monument point approximately 500 ft. distance from the island. This measurement will also be made on a nominally twice-daily basis. The positions of the island and ice sheet points will be determined using DGPS by Lounsbury and Associates. The accuracy of the positions will be approximately 0.10 ft. and the accuracy of the relative positions will be approximately 0.10 ft. Lounsbury will have a base station at Oliktok Dock or other location as required to achieve this accuracy.

The ice movements will be used by Sandwell to determine the safety of the operation and to evaluate the performance of the design.

3.3 REVISED DESIGN

The continued warmer than normal air temperatures resulted in further reductions in the end-of-season design ice thickness. The warmer temperatures also resulted in the spraying process being much less productive. As there was sufficient equipment on site, the designs were changed to incorporate chipped ice as part of the above water volume of the island. Chipped ice has a higher density than sprayed ice and thus less freeboard would be required to achieve the same on-bottom weight.

The islands are grounded in 7, 10 and 12 ft. of water and are designed to resist forces induced by motion of the natural first-year ice cover. The required island geometry is given in Table 3-3.

Figure 3-4 illustrates the island and the key geometric dimensions plus the ice force and resisting forces. As explained in the design report, the ice force is defined by:

$$\text{Ice Force} = \text{Design ice pressure} \times \text{design ice thickness} \times \text{contact width}$$

The resisting shear force at the bottom of the island in contact with the seabed is given as:

$$\text{Shear resistance} = \text{Net weight of ice} \times \tan(\phi)$$

Where ϕ is the internal friction angle of the seabed soil.




Figure 3-4 Spray Ice Island Cross Section

3.3.1 Design Ice Force

As explained in the design document, the ice force induced by the surrounding floating ice cover is based on an achievable ice thickness for this year of 5.7 ft. The 5.7 ft. was arrived at by projecting the ice thickness at the time of the initial survey in early January to the end of the season using historical temperature and ice growth data. However, the natural ice cover thickness is presently 40 inches or 3.3 ft. 10 holes drilled in the natural ice around Ivik island confirm this and the results are listed in Table 3-5.

**Table 3-5 Natural Ice Thickness adjacent to Ivik Island
February 10, 2003**

Latitude	Longitude	Ice Thickness (inches)
70 30 35.0	150 10 30.4	40
70 30 26.3	150 10 27.3	41
70 30 20.3	150 10 26.5	44
70 30 13.9	150 10 53.1	33
70 30 12.8	150 11 06.7	43
70 30 12.9	150 11 20.2	40
70 30 29.9	150 12 05.9	41
70 30 33.8	150 12 00.7	43
70 30 40.7	150 11 48.6	40
70 30 45.2	150 11 42.7	41
	Average	40.6

Using the same historical projection for design, the ice can only reach 5.0 ft. by April 20. Thus the design ice thickness is reduced to this amount based on the real-time information now available. The resulting change in geometry to the island is shown in Table 3-6.

Table 3-6 Ivik Spray Ice Island Design

initice	3.3 ft.	Initial ice thickness
depth	16 ft.	Water depth
h	5 ft.	Spring ice pack thickness
bwtaper	44 ft.	Below water taper width
p	200 psi	Design ice pressure
awden	38 lb/ft ³	Above water ice density
bwden	57.8 lb/ft ³	Below water density
swden	64 lb/ft ³	Sea water density
cohesion	0 psf	Soil cohesion
phi	33 deg	Soil internal friction angle

Island Core Radius (ft)	Island Freeboard (ft)	Effective Width (ft)	Above Water Taper Width (ft)	Ice Force (kips)	Sea Water Density (lb/ft ³)	Above Water Spray Ice Density (lb/ft ³)	Below Water Ice Density (lb/ft ³)	Spray Ice Vol Above Water (ft ³)	Vol Below Water (ft ³)	Core Volume (ft ³)	Wt on Bottom (kips)	Bottom Contact Area (ft ²)	Sliding Resistance (kips)	Factor of Safety	Volume Spray Ice (ft ³)
300	18.9	675	37.7	97,258	64	38	57.8	6,028,047	4,335,969	8,920,956	202,183	270,998	131,299	1.35	9,973,507

Comparing with Table 3-3b of the design report, the island freeboard above design water level changes from 20.6 ft. to 18.9 ft. as a result of the reduced ice force.

Above Water Ice Density

As of February 11, the island has been completed to a height above water of 10 ft. It was planned to complete the remainder of the island using chipped ice hauled from a separate location which was then soaked with water after being placed on the island. Measurements on the ice roads being built for the Thetis project show that the placed chipped ice has a density of 52 lb/ft³ vs. the spray ice density of 38 lb/ft³. Thus the required net weight on bottom to produce a shear force sufficient to resist the ice force with a factor of safety of 1.35 can be produced with less ice freeboard or volume. The resulting island geometry is listed in Table 3-7 below.

Table 3-7 Combined Spray and Chipped Ice Island

initice	3.3 ft.	Initial ice thickness
depth	16 ft.	Water depth
h	5 ft.	Spring ice pack thickness
bwtaper	44 ft.	Below water taper width
p	200 psi	Design ice pressure
awden	38 lb/ft ³	Above water ice density
bwden	57.8 lb/ft ³	Below water density
swden	64 lb/ft ³	Sea water density
cohesion	0 psf	Soil cohesion
phi	33 deg	Soil internal friction angle

Island Core Radius (ft)	Island Freeboard (ft)	Effective Width (ft)	Above Water Taper Width (ft)	Ice Force (kips)	Sea Water Density (lb/ft ³)	Spray Ice Ht. (ft)	Ice Chip Density (lb/ft ³)	Below Water Ice Density (lb/ft ³)	Spray Ice Vol Above Water (ft ³)	Chip Ice Vol (ft ³)	Vol Below Water (ft ³)	Core Volume (ft ³)	Wt on Bottom (kips)	Bottom Contact Area (ft ²)	Sliding Resistance (kips)
300	16.6	666	33.1	95,942	64	10	52	57.8	3,281,348	1,939,165	4,202,101	8,274,970	199,475	262,631	129,540

The required ice island freeboard, considering both the design natural ice cover thickness of 5 ft. and the increased density of the placed ice chips, is 16.6 ft.

In conclusion, approval was sought from ADEC to modify the design of the Thetis spray ice islands in accordance with insitu measurements of current natural ice cover thickness and with revised materials to be used in construction. The factor of safety against sliding of the islands will remain 1.35 as required by API and other accepted design codes and standards. Approval from ADEC of the revised design was obtained.

3.4 ACCESS ROAD

The location of the ice access road is shown in Figure 2-1. This road will be grounded over the majority of its length. However, where it is not grounded, or where the bottom support is weak and questionable, the ice thickness required to support the heaviest load in a floating mode is required.

The heaviest load identified is Nabors Rig 27E substructure. The load footprints and distance between are shown in Figure 3-5. Using an allowable flexural stress in the ice of 72.5 psi, the ice thickness required to transport this load configuration in a floating mode is 12.5 ft.

This ice lies over between 1 and 2 feet of softer material, which is found on top of the stiff soil required to support the ice.




Figure 3-5 Nabors Rig 27E Substructure Footprint

4 Construction Methods and Transport

The drilling support and transport involved in this project involved the co-operation of several companies and the cumulative use of all their machinery. Peak provided the drilling support for Rig 3.

Peak and AIC were both hired to build the ice roads and islands. Peak (and CATCO) were responsible for 6 Natchiq and Ivik Islands and AIC was responsible for Oooguruk. Peak constructed the ice road from Oliktok point to Natchiq and AIC constructed the remaining ice road to Ivik and to Oooguruk.

4.1 SPRAYING

The spraying of the islands involved using large 200 psi pumps, which sprayed water over the island location for a certain length of time. Pumps for spraying the islands were supplied by CATCO and AIC. CATCO used one 3000 gpm pump mounted on vehicle and three 5000 gpm pumps, AIC used two 3000 gpm pumps. The pumps were then shut down so that the ice could cure and harden. The cycles usually consisted of half an hour of spray and then half an hour of curing. When the air temperature is lower more water could be sprayed and less time was needed for the curing. In warmer weather, the opposite applies, with less spraying and more curing time needed. The spray ice density is also affected by the air temperature during spraying with warmer temperatures generally producing higher density material.

4.2 CHIPS AND WATER HAULING

Once the spraying was completed, Cats were used to level the island tops. In this particular project, D6's were used (40,000 lbs tractors) as well as D5's. Peak then used Kenworth trucks on Ivik and Natchiq to haul chips. Water was moved in 100 and 300-barrel water trucks. AIC used B70's and Maxi-hauls for the chips and water hauling on Oooguruk. AIC also assisted with chip hauling to Ivik.

The Chip producing process consists of creating chips at sites away from the ice islands and roads using a chipper, which is a converted asphalt stripper. Once the ice had been disaggregated it was loaded into trucks and transported to the ice islands and roads. The chips of ice were dumped on the ice and leveled and water was poured over the chips so that the voids were filled with water which quickly froze because of the available capacity in the frozen chips.

The benefit of using chips in the building of ice islands and roads is that the ice and/or air temperature does not need to be as low as required with spraying. This is due to the fact that the ice chips absorb the heat of freezing and less water has to be frozen.

Because of the outflow of the Colville River, the ice borrow sites for the chipped ice were found that had a salinity much lower than first year sea ice of comparable thickness ice. Thus the chipped ice was essentially fresh water ice. For most of the access road construction, fresh

water was used. An exception was in the offshore section of the Natchiq access road where a low pressure pumper unit was used to provide an initial layer of sea water. This significantly reduced the amount of fresh water that had to be hauled for the road construction.

4.3 VERIFICATION

Once the construction was completed, the safety and strength of the islands and roads had to be verified. In this case, the thickness of the ice was measured at a number of points along the roadway and also in the islands themselves. The continuity of the ice was evaluated and the islands and roads were inspected to ensure that no cracks or other unconformities were present to hamper the transportation of the rigs. The density of the ice in the islands and roads were measured. Figures 4-1 and 4-2, below shows the spray ice density data collected from all three islands: Ivik, Ooguruk and Natchiq and the Ooguruk Core Density taken on March 17. For all of the collected density data and supporting information refer to Appendix A. Figure 4-1 shows the measured ice density data, the blue bars represent the collected data and the purple bars represent a Gaussian fit to the data. As can be seen from Figure 4-1 the data are slightly skewed with a tail on the high density side. The scatter in the data is from two major sources, differences in actual material density and errors in the actual density measurement. It is estimated that the source density variation dominates. The spray ice density is known to be a strong function of the air temperature during the spraying process.




Figure 4-1 Measured Spry Ice Density




Figure 4-2a




Figure 4-2b

5 Construction

5.1 IVIK ICE ISLAND:

Construction

Spraying of Ivik Ice Island was started on January 24 2003. Three pumps were used for the spraying: one 3000 gpm pump and two 5000 gpm pumps. Patterns of 15 minutes of spraying followed by 1 hour of curing. By January 25, the whole island had been covered by layer of spay ice and the spraying continued. Total ice thickness was recorded on January 26, yielding average ice thickness of 5 feet thus an average of 2.3 feet of ice buildup was obtained since spraying started.

On January 28, the island was drilled and the average ice thickness over the core was measured to be 6.4 feet, a build up rate of 0.75 ft/day. It was concluded that at this rate the island would not be ready for the drilling schedule, which is illustrated below in Table 5-1.

Table 5-1 Revised Drilling Schedule

ID	Task Name	Duration	Start	Finish	Schedule																	
					12/22	12/29	1/5	1/12	1/19	1/26	2/2	2/9	2/16	2/23	3/2	3/9	3/16	3/23	3/30	4/6	4/13	4/20
1	Engineering	20 days?	Mon 12/30/02	Fri 1/24/03																		
2																						
3	Ivik Site Prep	4 edays?	Wed 1/15/03	Sun 1/19/03																		
4	Build ice road to Ivik	30 edays?	Mon 1/13/03	Wed 2/12/03																		
5	Mob pumps to Ivik	1 eday	Thu 1/23/03	Fri 1/24/03																		
6	Spray Ivik Island	25 edays?	Fri 1/24/03	Tue 2/18/03																		
7	Prepare Isl - Cellar etc.	5 edays?	Tue 2/18/03	Sun 2/23/03																		
8	Rig up and drill well-test-log	15 edays?	Sun 2/23/03	Mon 3/10/03																		
9																						
10	Natchiq site prep	4 edays?	Wed 1/22/03	Sun 1/26/03																		
11	Mob pumps to Natchiq	1 eday?	Tue 2/4/03	Wed 2/5/03																		
12	Spray Natchiq	25 edays?	Wed 2/5/03	Sun 3/2/03																		
13	Prepare Isl - Cellar etc.	5 edays?	Sun 3/2/03	Fri 3/7/03																		
14	Rig up and drill well-test-log	15 edays?	Mon 3/10/03	Tue 3/25/03																		
15																						
16	Oooguruk site prep	4 edays?	Wed 1/22/03	Sun 1/26/03																		
17		1 eday?	Thu 1/23/03	Fri 1/24/03																		
18	Spray Oooguruk	25 edays?	Fri 1/24/03	Tue 2/18/03																		
19	Finish ice road	10 edays?	Wed 2/12/03	Tue 2/25/03																		
20	Prepare Isl - Cellar etc.	5 edays?	Tue 2/18/03	Sun 2/23/03																		
21	Rig up and drill well-test-log	15 edays?	Sun 2/23/03	Mon 3/10/03																		

A number of suggestions to stay on schedule were provided by Sandwell, which included:

- Another 5000 gpm pump be provided by CATCO.
- The Rolligon pump be removed from the road to the west and returned to the island.
- That an AIC pump be moved from Oooguruk to Ivik.

Adjustments were made at Ivik on January 31 to produce more ice buildup by adding a 5000 gpm pump and using the 3000 gpm pump on the road and the ramp onto the island.

With the lowering of the temperature, the pumping frequency and pumping duration were increased on February 2.

On February 3, the air temperature increased and the pumping frequency and duration had to be restored to lower levels. An elevation survey was conducted and the average island height increased to 15.9 feet from 12.7 feet since February 1. From February 4 to 7, spraying continued at a much lower frequency and duration because of high air temperature.

On February 8, however, spraying stopped and leveling of the island top started in preparation for hauling chips. High winds and temperature slowed work considerably from February 9 to 10. Cats, however, did continue to level the island and set the surface of the island up for chip hauling. On February 11, spraying was discontinued and Peak started hauling chips and water to the Ivik ramp area and prepared to build up the surface of the island to the final height.

From February 12 to 16, hauling of chips and water onto Ivik continued. As of February 17, the island was ready for the rig, with a final density of the chipped ice being 50 lb/ft³

On February 19, Rig 27E was brought onto Ivik Island from Oliktok Point.

Densities of the spray ice were also tested on 26 samples from the core and the resulting average ice density was 38 lb/ft³. The average salinity was 14 ppt with a range of 7.9 to 26.1

Data from Ivik's Island Settlement Survey can be seen in Table 5-2 and Figure 5-1. Note that in Figure 5-1 the data were obtained from DGPS Survey and that the scatter in the data points around the trend line is most likely due to systematic and/or random errors in the elevation measurements. It is very unlikely that the apparent rise in the island surface is a real effect. In addition GPS position measurements are less accurate in the vertical axis compared to the horizontal axis and the absolute accuracy may be effected by auroral activity




Figure 5-1. Ivik Post Construction Settlement

Table 5-2 Ivik Island Settlement Survey

Data from Survey using DGPS

				slope	-0.062					-0.034
				intercept	2361.881					1290.493
Monitor Pad 4				Monitor Pad 5						
Date	North	East	Elevation	Line	North	East	Elevation	Line		
20 Feb	6034850.80	477060.23	19.27	19.17	6035097.95	476791.93	18.26	18.20		
21 Feb	6034850.82	477060.24	19.00	19.11	6035097.91	476791.93	17.99	18.16		
22 Feb	6034850.77	477060.24	19.01	19.05	6035097.84	476791.91	18.12	18.13		
23 Feb	6034850.82	477060.22	19.05	18.99	6035097.92	476791.93	18.22	18.10		
24 Feb	6034850.74	477060.23	18.84	18.92	6035097.87	476791.95	18.02	18.06		
26 Feb	6034850.76	477060.24	18.85	18.80	6035097.86	476791.94	18.06	18.00		
28 Feb	6034850.72	477060.28	18.84	18.68	6035097.78	476791.93	18.12	17.93		
01 Mar	6034850.68	477060.20	18.47	18.61	6035097.82	476791.95	17.68	17.89		

Thermistor Data

On February 8, a hole was thermally drilled to install a thermistor. The ice was a maximum thickness of 30 feet at this point.

On February 19, Sandwell used a hot water drill to obtain an as-built thickness profile of the island, which showed that the island met the design requirements. The design requirements included specific thicknesses, continuity on the island (i.e. no holes or cracks on the surface of the island) and specific densities.

On February 20 to 24, a thermistor string was installed to monitor the island's temperature profile adjacent to the well and the settlement survey of the island started.

Drilling

Rig 27E started drilling on February 25 and the ice temperature profile in the island obtained, indicated satisfactory temperatures. Rig 27E continued drilling on Ivik until March 13, when it was moved to Oooguruk Island. Well testing on the island, continued after all Sandwell personnel had left the field on April 2.

5.2 OOOGURUK ICE ISLAND

Construction

Spraying of Oooguruk Ice Island started at the same time as Ivik Ice Island on January 24 2003. Initially a 3000 gpm pump supplied by AIC was used on Oooguruk, and started with patterns of 15 minutes of spraying were followed by 1 hour of curing.

On January 25, another 3000 gpm pump was added to the spraying of the island. By January 26, the average ice thickness was 5.3 feet, and there was 2.1 feet of average buildup since the

Sandwell

start of spraying. A pump had to be stopped at this time, due to the fact that there was a significant amount of wet, unfrozen material in one location.

On January 28, difficulties arose due to the fact that very wet material had been put down and not given the chance to cure before the next layer was put down. For this reason, there was as much as 40 inches of unfrozen material with a 10 to 15 inch crust. This was solved by changing the size of the pump nozzle from 3 3/8 inches to 2 inches. By doing this, the material produced was drier.

By January 31, the quality of the material made had greatly improved. February 2 brought a decrease in temperature, so the pumping frequency and duration was increased. AIC was advised to lower their nozzle angle and increase pumping times.

On February 3, an elevation survey was conducted, showing an average ice thickness of 8.2 feet, from 6.8 feet on 31 January. Five density measurements were also taken from samples of 2 cores and the resulting density was 36 lb/ft³.

Spraying continued on Oooguruk until February 9 when work came to a complete stop due to an increase in air temperature. Spraying, however, started again the next day at a moderate rate.

Intense spraying and leveling with 2 Cats continued on Oooguruk on February 17. The island had an average density of 39.5 lb/ft³.

Spraying continued until February 26, when leveling and the hauling of chips began.

Island Thickness

On March 4, Sandwell drilled the island and it showed that the island and ramp are well grounded. Total thickness of the island is between 31 and 32 feet. These numbers show that very little settlement of the island into the mud had occurred.

Drilling

On March 5, final grading on the rig area was being carried out on the island. The island was ready on March 7, and Rig 27E was brought onto Oooguruk on March 13. The drilling and well logging began on March 18 and was completed on March 27.

5.3 NATCHIQ ICE ISLAND:

Construction

Natchiq Ice Island was started On February 11, later than the other two islands. The CATCO spraying equipment was moved from Ivik onto Natchiq. The duration of each spray period on Natchiq was increased since temperatures were in the range of -7°C and -9°C. Cure times were 20 minutes.

Sandwell

From February 12 to 25, spraying and leveling continued on the island, which had an average density of 38.9 lb/ft³. Leveling and chip hauling started on February 26 and continued to March 4.

On March 5, rig mats were being moved onto Natchiq. March 6 brought the transport of miscellaneous supplies and the Rig 3 camp onto the island.

Thermistor

On March 17, Sandwell installed a thermistor string to monitor temperatures on the road to Natchiq. These showed that ice temperatures were normal.

Drilling

On March 7, Rig 3 was moved off Natchiq and over to Oooguruk with the help of a D6. Due to a problem with the ice road from Natchiq to Oooguruk, Rig 3 camp was moved back to Natchiq on March 8, where it stayed until March 11 when work on the road was complete.

Rig 3 was finally moved down the Natchiq road to the island on March 13 and reached the island on March 15, and prepared to spud. The rig started drilling and logging on March 18 and stopped on March 28.

Island Build-up rates

Table 5-3 and Figure 5-2 below show the elevation trends during construction for all three islands, Ivik, Oooguruk and Natchiq. The fastest build up rates were on Natchiq. This is a result of the larger pumping capacity and the construction coincided with a cold period. The regression data for Ivik is fitted to the period where chipped ice is being used for construction. Build up data were in general, obtained from GPS survey data and measure the location of the top surface of the island relative to BPMSL. Before the island is well grounded most of the constructed ice is submerged so that the top surface elevation does not represent actual build up.




Figure 5-2

Table 5-3

Average Height from survey data relative to BPMSL

Date	Ivik	Oooguruk	Natchiq	Average Build-up rate when well grounded			
				Ivik	Oooguruk	Natchiq	
24-Jan-03				ft/day	1.69	0.98	2.22
25-Jan-03				intercept	-63492.6	-36870	-83630.8
26-Jan-03							
27-Jan-03							
28-Jan-03							
29-Jan-03							
30-Jan-03							
31-Jan-03							
01-Feb-03	3.52						
02-Feb-03							
03-Feb-03	5.42	1.76					
04-Feb-03	6.42	1.29					
05-Feb-03		1.29					
06-Feb-03							
07-Feb-03	6.63	2.51					
08-Feb-03	6.85	2.20					
09-Feb-03	6.39	3.11					
10-Feb-03	7.14						
11-Feb-03	6.78	4.67					
12-Feb-03	7.42	5.04					
13-Feb-03	8.24	5.64			9.2	5.2	
14-Feb-03	11.38		6.97		10.9	6.2	
15-Feb-03	12.57				12.6	7.2	
16-Feb-03	15.12		9.64		14.3	8.2	9.9
17-Feb-03	16.02	8.95			15.9	9.1	12.1
18-Feb-03	18.19	9.82	14.70		17.6	10.1	14.3
19-Feb-03	18.28	10.62			19.3	11.1	16.5
20-Feb-03		12.08	18.64			12.1	18.7
21-Feb-03		13.88				13.1	21.0
22-Feb-03		13.75	23.14			14.0	23.2
23-Feb-03		14.60				15.0	
24-Feb-03		15.95				16.0	
25-Feb-03						17.0	
26-Feb-03		18.36				17.9	
27-Feb-03							
28-Feb-03							
01-Mar-03							
02-Mar-03							
03-Mar-03							
04-Mar-03							
05-Mar-03							
06-Mar-03							

Regression Line

5.4 IVIK ICE ROAD

With the decision to reroute the ice road to Ivik and Oooguruk, along the shore rather than directly from Natchiq, construction of the roads started on January 26. It was agreed that AIC would build the road from the west using chips and CATCO would build from the east to about ½ mile from Ivik.

On January 31, the CATCO 3000 gpm pump started spraying the road and ramp off of Ivik Island and continued until February 4 when the pump had to be brought to Deadhorse for repairs. Chips were also being used to build the road to Ivik. The amount of chips and water needed for the building of this road is given in Table 5-4 and Figure 5-3.

Table 5-4 Ivik Road from Beach to Island

Date	Peak Days Chips (yards)	Peak Nights Chips (yards)	Peak Days water (gal)	Peak Nights water (gal)	AIC Daily Chips (yard)	Daily chips (yards)	Daily water (gal)	Cumulative chips (yard)	Cumulative water (gal)
11 Feb		4410		266070	0	4410	266070	4410	266070
12 Feb	3700	3850	627900	708750	0	7550	1336650	11960	1602720
13 Feb	3625	3825	736050	662550	3625	11075	1398600	23035	3001320
14 Feb	5525	5550	823200	683550	3950	15025	1506750	38060	4508070
15 Feb	6275	6150	740250	759150	3925	16350	1499400	54410	6007470
16 Feb	6900	5430	701400	794850	1650	13980	1496250	68390	7503720
17 Feb	6720	6000	747600	632100	4080	16800	1379700	85190	8883420
18 Feb	7170	2520	599550	452550	1290	10980	1052100	96170	9935520




Figure 5-3a




Figure 5-3b

The pump returned on February 5, and continued spraying the ramp and road off Ivik. During this short break, AIC had most of the road to Ivik grounded and the last ½ mile was within 2 feet of being fully grounded.

On February 10, AIC had completed the island to Ivik. Sandwell drilled the approach road and ramp onto Ivik Island on February 15. There was a cap 4 to 6 feet on top of spray ice next to Ivik's perimeter. The ice was continuous from the ice surface down to the seabed. A Roligon drill was used to test the spray ice capacity and it supported the weight of the drill on the bit. Structurally, the approach road and ramp to Ivik were ready for the rig.

Problems arose on the Ivik access road on March 8 when the road was overloaded by Rig 3. The rig's front tires, broke through the ice and became stuck. The rig was removed and an alternate route around the rig was built.

5.5 OOOGURUK ICE ROAD:

On January 31, chips were being used to build the road to Oooguruk. On February 10, AIC, reached Ivik ice island and continued to proceed past the island towards Oooguruk. Peak then started to finish the link between the cul de sac and the Oooguruk ramp.

The construction of the road to Oooguruk was still under way on February 19, and continued until March 2 when the haul road to Oooguruk was surveyed for thickness and quality. The Data from this survey can be seen in Table 5-5. The road was deemed almost finished with minor

leveling required on March 3 and the maintenance and completion was worked on until March 7. Once completed, Rig 3 was moved onto Natchiq and continued to Oooguruk.

Problems arose on the Ivik access road on March 8 when the front tires of Rig 3 broke through the ice and the rig became stuck. The rig was removed and an alternate route around the rig was built. Once the rig was moved back to Natchiq, the road to Oooguruk was matted in the areas of the repairs and AIC repaired cracks and worked on the pad area and then laid mats down.

Table 5-5 Oooguruk Road Thickness Survey

02 Mar 03

Distance from Ivik Junction. Survey done with Catco thermal drill by PS, BG and JS

	East Side		West Side	
	Ice Thickness (ft)	Mud (ft)	Ice Thickness (ft)	Mud (ft)
0	13.3		12	1
0.1	14.5		14	0.8
0.2	15.0		14	0.5
0.3	15.0		13.5	1.5
0.4	13.6		14	1
0.5	13.0		14	1.5
0.6	14.7		14	
0.7	16.0	1	15.5	0.8
0.8	16.5	1	14.5	1
0.9	16.5		14.5	1
1	17.0		14	3
1.1	17.0		14	1
1.2	16.0		16	4
1.3	15.6		14.5	1.5
1.4	13.0	2.5	13.5	2
1.5	15.0		Toe 13	2
1.6	19.0		Ramp 18.5	

5.6 NATCHIQ ICE ROAD

On February 19, Peak continued on the road to Natchiq and started hauling chips to complete the road from the beach. The road was deemed well grounded on March 3. On March 7, once the maintenance was completed, Rig 3 was moved onto Natchiq Island, and continued onto Oooguruk. The rig had to be moved back to Natchiq on March 8, when the front tires of Rig 3 broke through the ice.

All the roads were constantly maintained and repaired until the rigs were moved of the island and back onto shore.

Table 5-6 and Figure 5-4 show the amount of chips and water hauled to build the Natchiq ice road.

Table 5-6 Natchiq Road from Beach to Island

Target 102400

Date	Peak Days Chips (yards)	Peak Nights Chips (yards)	Peak Days water (gal)	Peak Nights water (gal)	Daily chips (yards)	Daily water (gal)	Cumulative chips (yard)	Cumulative water (gal)	cum chips from	completion date
19 Feb	3540	2280	599550	206850	5820	8E+05	5820	806400	21.Feb	
20 Feb	3540	3780	662550	573300	7320	1E+06	13140	2042250		
21 Feb	3660	3390	282450	354900	7050	6E+05	20190	2679600	7050	07.Mar
22 Feb	4410	3900	417900	390600	8310	8E+05	28500	3488100	15360	06.Mar
23 Feb	4380	4260	469350	231000	8640	7E+05	37140	4188450	24000	05.Mar
24 Feb	4440	4140	506100	341250	8580	8E+05	45720	5035800	32580	05.Mar
25 Feb	4320	3720	348600	330750	8040	7E+05	53760	5715150	40620	05.Mar
26 Feb	3300	2790	382200	319200	6090	7E+05	59850	6416550	46710	05.Mar
27 Feb	4230	3150	462000	402150	7380	9E+05	67230	7280700	54090	05.Mar
28 Feb	3600	2610	437850	449400	6210	9E+05	73440	8167950	60300	05.Mar
01 Mar	3780	2400	522900	445200	6180	1E+06	79620	9136050	66480	05.Mar
02 Mar	3,210	2220	540750	401100	5430	9E+05	85050	10077900	71910	05.Mar
04 Mar	3990	2910	481950	483000	6900	1E+06	91950	11042850	78810	05.Mar
05 Mar	1890	3330	541800	463050	5220	1E+06	97170	12047700	84030	05.Mar




Figure 5-4




Figure 5-4b

The height above water level to which the grounded ice roads were constructed, ensured that they would not refloat during a 2 ft storm surge event. Figure 5-5 shows sea level data collected at the STP Plant as part of the NOAA program.

**Water Levels - Prudhoe Bay STP
Nov 2002 - February 2003**




Figure 5-5

6 Performance

6.1 ROADS

The roads along the shore presented no problem in the transportation of the Rigs, the offshore roads, however, did present a problem with Rig 3. This was due to the fact that Rig 3 was far heavier than Rig 27E. Rig 27E was approximately 1.5×10^6 lbs while Rig 3 was approximately 2.7×10^6 lbs.

The ice road could not support Rig 3 and the wheels broke through and the rig became stuck. This was due to the fact that under the ice was a layer of mud between 8 and 12 inches. As the rig moved, the ice moved down through the soft material until it reached stiffer material. By this point, however, the ice had bent so much that it past its limit of elasticity and reached its breaking point. AIC constructed an alternate route around the rig for traffic use until the main road was repaired. The holes were eventually filled and the damaged areas were repaired.

6.2 ISLANDS

Over the course of the period that work was done on the Islands and Roads, the movement of the islands was recorded with the use of differential GPS measurements. The movement data can be found in Appendix B, while Figure 6-1 shows the Net Ice Motion data and the Net Movement Vectors. Note that the movement data are obtained from monuments placed on the floating level ice adjacent to the islands. These monuments were typically 0.5 mile from the island centers. Post construction measurements also obtained from differential GPS data showed negligible horizontal movement of the islands themselves.

In Figure 6-1a the trend lines are based on the net movement being proportional to the square root of time. Such a functional dependence is predicted from a random-walk model of the ice movement. Data in Figure 6-1b shows that that the movement direction as well as the magnitude was different at each site. Note that the data shown in figures 6.1 are only up to March 15. See Appendix C1 C2 and C3 for the data for the complete monitoring period. The termination data for sea ice movement varied with each site. At the termination of monitoring the ice movements were 3.11, 1.37 and 1.31 ft from the original position for Ivik, Oooguruk and Natchiq respectively.

See Appendix D4 for data on in-situ ice temperatures.

See Appendix E for selected photographs illustrating the project.

NET ICE MOTION DATA: THETIS ISLAND PROJECT 2003




Figure 6-1a

NET MOVEMENT VECTORS




Figure 6-1b

7 References

Bugno W., Masterson D. M., Kenny J., Gamble R. (1990), "Karluk Ice Island" OMAE 1990, Vol. 4

Funegard, E.G., Nagel, R.H. and Olson, G.G., (1987), "Design and Construction of the Mars Spray Ice Island", Offshore Mechanics and Arctic Engineering (OMAE), Houston, TX.

Geotech (1988), "Chevron Karluk Ice Island – Design Basis", November 1988.

Goff R. D., Masterson D. M. (1986), "Construction of a Sprayed Ice Island for Exploration", OMAE 1986.

Lawrence et al (1992), "Spray Ice" by Lawrence, Funegard, Poplin, Sisodiya, Weaver for the United States Minerals Management Service Technology Assessment and Research Branch, July 1992.

Weaver J. S., (1988), "The Design, Construction and Verification of the Angasak Spray Ice Exploration Island" OMAE, 1988 Vol. 4 pp. 177-183.



Appendix A

APPENDIX A1 ALL SPRAY ICE DENSITIES

Density (lb/ft ³)						0.118			error ²			
Ivik	Oooguruk	Natchiq				3.689			5.161150876	0.12	3.7	5.392404
42.6	37.1	40.7	mean	40.9	25	0	3.4E-05			0.11	3.7	5.68403
39.1	37.9	43.0	stdev	5.2	26	0	0.00013	0.023616	0.000557731	0.13	3.7	5.612113
45.4	43.0	44.3	min	29.5	27	0	0.00043	0.073762	0.005440862	0.115	3.7	5.464027
36.6	32.2	34.9	max	57.2	28	0	0.00125	0.200234	0.040093602	0.125	3.7	5.449926
38.5	39.9		count	245	29	0	0.0032	0.478681	0.229135363	0.12	3.65	7.761937
35.1		40.7			30	2	0.00736	1.019556	0.961271024	0.12	3.69	5.175588
38.0		45.4			31	0	0.01534	1.954829	3.821356207	0.12	3.71	5.951197
		44.3			32	4	0.02924	3.40503	0.35398963	0.12	3.68	5.356063
36.7	45.1				33	4	0.05141	5.43251	2.052085646	0.11	3.69	5.345287
32.4	53.0	40.9			34	4	0.08406	7.997029	15.97624089	0.115	3.69	5.185718
41.0	51.7				35	12	0.12868	10.93355	1.137314391	0.12	3.695	5.236059
39.3	49.9	36.4			36	14	0.18569	13.9659	0.001162808	0.118	3.689	5.161151
43.5	51.8	39.1			37	14	0.25408	16.75602	7.595666727			
41.5	43.1	34.5			38	18	0.33152	18.97421	0.949094418			
40.9	44.6	37.1			39	26	0.41466	20.36795	31.72003245			
45.0	34.1				40	22	0.49959	20.80897	1.418560876			
41.3	33.0	33.3			41	20	0.58248	20.30704	0.094276471			
39.7	32.0	34.7			42	20	0.66	18.99201	1.016040949			
43.3	47.1	39.6			43	12	0.72969	17.07402	25.74569986			
38.0	43.7				44	14	0.79008	14.79589	0.633440618			
35.8	43.5	57.2			45	8	0.84065	12.39054	19.27681701			
38.5	47.5	46.9			46	9	0.88167	10.05071	1.103982503			
42.3					47	6	0.91398	7.913935	3.663148913			
47.7	37.5	38.7			48	8	0.93872	6.060895	3.760126279			
41.1	36.4	40.3			49	8	0.95718	4.522954	12.08985224			
42.7	29.8	47.1			50	4	0.97062	3.294438	0.497817582			
42.0	31.3	41.3			51	4	0.9802	2.345811	2.736341021			
38.2		41.3			52	6	0.98687	1.635258	19.05097369			
41.2	32.7				53	1	0.99143	1.117493	0.013804702			



Density (lb/ft ³)					0.118			error ²				
Ivik	Oooguruk	Natchiq			3.689			5.161150876	0.12	3.7	5.392404	
42.6	37.1	40.7	mean	40.9	25	0	3.4E-05		0.11	3.7	5.68403	
39.1	37.9	43.0	stdev	5.2	26	0	0.00013	0.023616	0.000557731	0.13	3.7	5.612113
45.4	43.0	44.3	min	29.5	27	0	0.00043	0.073762	0.005440862	0.115	3.7	5.464027
36.6	32.2	34.9	max	57.2	28	0	0.00125	0.200234	0.040093602	0.125	3.7	5.449926
38.5	39.9		count	245	29	0	0.0032	0.478681	0.229135363	0.12	3.65	7.761937
35.1		40.7			30	2	0.00736	1.019556	0.961271024	0.12	3.69	5.175588
38.0		45.4			31	0	0.01534	1.954829	3.821356207	0.12	3.71	5.951197
		44.3			32	4	0.02924	3.40503	0.35398963	0.12	3.68	5.356063
36.7	45.1				33	4	0.05141	5.43251	2.052085646	0.11	3.69	5.345287
32.4	53.0	40.9			34	4	0.08406	7.997029	15.97624089	0.115	3.69	5.185718
41.0	51.7				35	12	0.12868	10.93355	1.137314391	0.12	3.695	5.236059
39.3	49.9	36.4			36	14	0.18569	13.9659	0.001162808	0.118	3.689	5.161151
43.5	51.8	39.1			37	14	0.25408	16.75602	7.595666727			
41.5	43.1	34.5			38	18	0.33152	18.97421	0.949094418			
40.9	44.6	37.1			39	26	0.41466	20.36795	31.72003245			
45.0	34.1				40	22	0.49959	20.80897	1.418560876			
41.3	33.0	33.3			41	20	0.58248	20.30704	0.094276471			
39.7	32.0	34.7			42	20	0.66	18.99201	1.016040949			
43.3	47.1	39.6			43	12	0.72969	17.07402	25.74569986			
38.0	43.7				44	14	0.79008	14.79589	0.633440618			
35.8	43.5	57.2			45	8	0.84065	12.39054	19.27681701			
38.5	47.5	46.9			46	9	0.88167	10.05071	1.103982503			
42.3					47	6	0.91398	7.913935	3.663148913			
47.7	37.5	38.7			48	8	0.93872	6.060895	3.760126279			
41.1	36.4	40.3			49	8	0.95718	4.522954	12.08985224			
42.7	29.8	47.1			50	4	0.97062	3.294438	0.497817582			
42.0	31.3	41.3			51	4	0.9802	2.345811	2.736341021			
38.2		41.3			52	6	0.98687	1.635258	19.05097369			
41.2	32.7				53	1	0.99143	1.117493	0.013804702			

APPENDIX A2: ROAD ICE DENSITY

Date	Location	Designation	No.	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.f)	Stake	Salinity (ppt)
8 Feb 03	70 30 08 150 13 03	A2	1	5	3	5	3	871	0.869	54.3		
			2	5	4	5	3	871	0.864	54.0		
			3	5	12	5	11	911	0.824	51.5		
			4	5	8	5	7	890	0.842	52.6		
			5	5	7	5	7	916	0.872	54.5		
	70 29 57 150 14 10	A1	1	5	7	5	7	894	0.851	53.2	A1	0.4
			2	4	15	4	12	801	0.856	53.5		0.0
			3	5	6	5	6	909	0.875	54.7		0.3
			4	4	14	4	13	750	0.801	50.1		3.4
			5	5	7	5	7	931	0.886	55.4		0.1
						mean	0.854	53.4		0.8		
						stdev	0.024	1.5		1.3		
8 Feb 03	70 27 03 150 12 07	P4	1	5	13	5	13	851	0.758	47.3		
			2	4	12	4	13	732	0.792	49.5		
			3	4	9	4	8	719	0.821	51.3		
			4	6	1	6	1	898	0.766	47.9		
	70 26 43 150 11 50	P3	1	5	12	5	11	857	0.775	48.5	P3	0.0
			2	5	15	5	14	977	0.856	53.5		0.3
			3	5	14	5	14	858	0.756	47.2		1.6
			4	5	8	5	7	930	0.880	55.0		2.2
	70 26 07 150 11 02	P2	1	5	5	5	6	812	0.786	49.1		
			2	5	11	5	11	904	0.822	51.4		
3			4	8	4	8	765	0.880	55.0			
4			4	5	4	4	714	0.863	53.9			
70 26 00 150 08 52	P1	1	5	7	5	7	902	0.858	53.6			
		2	5	3	5	3	834	0.832	52.0			

Sandwell

Date	Location	Designation	No.	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.f t)	Stake	Salinity (ppt)
			3	5	5	5	5	898	0.875	54.7		
			4	4	11	4	11	808	0.892	55.7		
								mean	0.826	51.6		1.0
								stdev	0.048	3.0		1.0
18 Feb 03	100 ft NE of IVIK Ramp	1	1	5	6	5	6	856	0.824	51.5		
			2	5	9	5	9	942	0.876	54.8		
			3	5	1	5	0	836	0.860	53.7		
	mid way Ivik ramp and road to Oooguruk	1	1	5	1	5	1	821	0.839	52.4		
			2	4	15	4	12	804	0.859	53.7		
			3	2	11	2	11	443	0.853	53.3		
								mean	0.852	53.2		
								stdev	0.02	1.1		
								overall mean	0.839	52.5		
								stdev	0.039	2.5		
								stderror	0.007	0.4		
								samples		32		

APPENDIX A3: NATCHIQ ICE ISLAND DENSITY DATA

Date	Location	top = 1								NATCHIQ Overall Statistics						
		Number	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)				
13 Feb 03	1	1	4	15	4	13	614	0.652	40.7	mean	41.0	#DIV/0!				
		2	4	12	4	13	635	0.687	43.0							
		2	3	12	3	15	526	0.708	44.3							
		4	4	14	4	12	520	0.559	34.9							
	2	1	4	13	4	13	605	0.651	40.7				stderr	0.5	#DIV/0!	
		2	4	6	4	2	596	0.726	45.4				min	33.3	0.0	
		3	3	8	3	12	497	0.709	44.3				max	57.2	0.0	
	14 Feb 03	3	1	4	14	4	15	621	0.655				40.9	stdev	4.9	#DIV/0!
			2	1	5	5	5	6	601				0.582	36.4	samples	91
2				5	0	4	14	597	0.626	39.1	cores	20	3			
3				4	8	4	8	480	0.552	34.5	days	7				
1		4	3	8	3	9	405	0.593	37.1							
		1	1	5	13	5	9	586	0.533	33.3						
		2	3	4	3	9	366	0.556	34.7							
16 Feb 03		7E	3	3	5	3	10	425	0.634	39.6						
			1	4	2	3	14	707	0.915	57.2						
		NS-14	2	3	12	3	12	544	0.751	46.9						
			1	4	12	4	13	572	0.619	38.7						
			2	4	13	4	13	599	0.644	40.3						
	3		4	6	4	4	628	0.754	47.1							

Sandwell

Date	Location	top = 1					Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Salinity (ppt)	NATCHIQ Overall Statistics	
		Number	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)					Density (lb/cu.ft)	Salinity (ppt)
		4	5	8	5	6	695	0.661	41.3			
		5	5	7	5	9	703	0.661	41.3			
17 Feb 03	NS8	1	4	2	4	0	518	0.660	41.2			
		2	4	15	4	15	638	0.669	41.8			
		3	5	1	5	0	605	0.622	38.9			
	E7	1	5	3	5	3	586	0.585	36.5			
		2	3	3	3	3	397	0.644	40.3			
		3	3	5	3	11	544	0.804	50.3			
		4	3	7	3	8	446	0.665	41.6			
	F6	1	5	12	5	14	749	0.667	41.7			
		2	2	8	2	7	394	0.826	51.6			
		3	2	9	2	9	438	0.884	55.3			
	F4	1	5	14	5	13	739	0.654	40.9			
		2	5	3	5	2	607	0.609	38.1			
		3	4	13	4	12	532	0.576	36.0			
		4	2	15	3	0	335	0.584	36.5			
	20 Feb 03	3	1	4	4	4	1	648	0.807	50.4		
			2	3	3	3	1	464	0.768	48.0		
3			2	13	2	15	420	0.756	47.2			
2		1	3	5	3	8	478	0.726	45.4			
		2	3	4	3	1	408	0.669	41.8			
		3	4	9	4	11	683	0.764	47.8			

Sandwell

Date	Location	top = 1					Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Salinity (ppt)	NATCHIQ Overall Statistics	Density (lb/cu.ft)	Salinity (ppt)
		Number	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)							
	1	1	4	7	4	9	603	0.693	43.3				
		2	5	1	5	1	657	0.672	42.0				
		3	4	11	4	11	592	0.653	40.8				
		4	4	15	5	0	599	0.624	39.0				
22 Feb 03	70 28 51.2 150 06 35.5	1	3	15	4	0	559	0.729	45.6	fresh			
		2	3	10	3	8	535	0.777	48.6				
		3	3	12	3	13	548	0.750	46.9				
		4	4	2	4	1	606	0.766	47.9				
	70 28 51.4 150 06 21.6	1	3	6	3	6	378	0.580	36.2	reworked			
		2	3	10	3	10	410	0.585	36.6				
		3	3	11	3	11	452	0.634	39.6				
		4	3	0	3	0	370	0.638	39.9				
		5	3	2	3	1	330	0.552	34.5				
		6	3	7	3	7	444	0.668	41.8				
		7	3	8	3	8	437	0.646	40.4				
	70 28 47.7 150 06 24.6	1	3	3	3	3	463	0.752	47.0	fresh			
		2	3	7	3	8	417	0.622	38.9				
		3	2	14	2	14	344	0.619	38.7				
		4	3	13	3	13	444	0.603	37.7				
		5	4	2	4	1	463	0.585	36.6				
		6	4	7	4	8	549	0.636	39.7				
26 Feb 03	3	1	3	5	3	5	416	0.650	40.6				
		2	2	8	2	10	336	0.678	42.4				
		3	3	1	3	1	361	0.610	38.1				
		4	3	0	2	14	367	0.646	40.4				

Sandwell

Date	Location	top = 1								NATCHIQ Overall Statistics	
		Number	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)
		5	3	14	3	14	422	0.564	35.2		
		6	3	1	3	1	352	0.595	37.2		
		7	2	13	2	13	299	0.550	34.4		
		8	3	1	3	1	337	0.569	35.6		
		9	1	13	1	13	191	0.545	34.1		
	2	1	2	13	2	14	314	0.571	35.7		
		2	2	9	2	3	264	0.575	35.9		
		3	3	8	3	8	424	0.627	39.2		
		4	4	0	3	15	483	0.630	39.4		
		5	2	13	2	11	349	0.657	41.0		
		6	3	1	2	15	310	0.535	33.4		
		7	2	13	2	14	337	0.613	38.3		
		8	2	12	2	13	306	0.569	35.6		
		9	2	14	2	14	312	0.562	35.1		
		10	1	13	1	14	196	0.550	34.4		
	1	1	3	7	3	8	471	0.703	43.9		
		2	2	5	2	8	322	0.692	43.3		
		3	3	9	3	9	502	0.729	45.6		
		4	3	8	3	8	479	0.708	44.3		
		5	4	5	4	5	527	0.632	39.5		
		6	4	3	4	3	549	0.678	42.4		
		7	2	8	2	5	310	0.667	41.7		
		8	4	15	4	14	665	0.701	43.8		
		9	2	15	3	0	389	0.678	42.4		



APPENDIX A4: IVIK ICE ISLAND DENSITY DATA

Date	Stake No.	top = 1	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Stake	Salinity (ppt)	Daily Statistics		IVIK Overall Statistics					
												Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)	Days			
02 Feb 03	G5	1	3	13	4	0	514	0.681	42.6			mean	39.3	14.0	mean	40.1	12.3		
		2	5	9	5	10	676	0.625	39.1			min	35.1	7.9	stderr	0.6	1.5		
		3	3	9	3	9	500	0.726	45.4			max	45.4	26.1	min	31.7	7.9		
	G5	1	6	3	6	3	701	0.586	36.6	G5	26.1	stdev	3.5	8.3	max	49.7	26.1		
		2	5	14	5	15	704	0.617	38.5	12.6	samples	7	4	stdev	4.0	5.0			
		3	5	2	5	5	567	0.562	35.1	7.9	stderr	1.3	4.1	samples	49	11			
		4	5	3	5	3	609	0.607	38.0	9.5	cores	2	1	cores	12	44			
																days	3		
	03 Feb 03	D6	1	4	4	4	3	479	0.588	36.7	D6	14.7	mean	40.4	11.3	IVIK and OOGURUK			
			2	4	0	4	14	444	0.518	32.4		8.4	min	32.4	8.4				
3			4	10	4	11	591	0.657	41.0	12.4		max	47.7	14.7					
4			4	15	4	14	596	0.629	39.3	11.3		stdev	3.3	2.0	mean				40.8
5			4	9	4	9	614	0.696	43.5	11.7		samples	26	7	stderr				0.6
6			3	12	3	11	477	0.664	41.5	10.6		stderr	0.6	0.8					
7			4	5	4	5	545	0.654	40.9	9.8		cores	6	1					
E7		1	4	4	4	3	587	0.720	45.0										
		2	4	14	5	0	630	0.660	41.3										
		3	4	2	3	15	495	0.635	39.7										
F6		4	4	14	4	14	652	0.692	43.3										
		5	4	14	4	14	573	0.608	38.0										
		1	5	3	5	2	570	0.572	35.8										
G5		2	5	0	4	15	592	0.617	38.5										
		3	4	2	4	2	539	0.676	42.3										
		4	3	7	3	9	516	0.763	47.7										
		1	5	4	5	3	663	0.657	41.1										
G5		2	5	6	5	6	709	0.683	42.7										
		3	4	0	3	12	503	0.672	42.0										
		4	5	1	5	1	598	0.611	38.2										

Sandwell

Date	Stake	No.	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Stake	Salinity (ppt)	Daily Statistics		IVIK Overall Statistics		
												Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)	
	H4	1	3	13	3	10	474	0.660	41.2							
		2	5	1	5	2	610	0.620	38.7							
		3	4	1	3	15	462	0.598	37.4							
		4	3	12	3	12	433	0.597	37.3							
	F4	1	4	7	4	7	555	0.647	40.4							
		2	4	12	4	14	681	0.732	45.8							
05 Feb 03	F4	1	4	5	4	9	470	0.548	34.3			mean	39.9	#DIV/0!		
		2	2	8	2	10	326	0.658	41.1			min	31.7	0.0		
		3	5	10	5	11	658	0.602	37.6			max	49.7	0.0		
	H4	1	5	9	5	8	748	0.700	43.7			stdev	5.2	#DIV/0!		
		2	4	9	4	8	540	0.617	38.5			samples	16	0		
		3	3	11	3	12	469	0.653	40.8			stderr	1.3	#DIV/0!		
		4	4	12	4	13	536	0.580	36.3			cores	4	0		
		5	5	11	5	7	654	0.608	38.0							
	G5	1	5	13	5	14	812	0.719	44.9							
		2	3	11	3	11	567	0.796	49.7							
		3	4	2	4	2	618	0.775	48.5							
		4	5	14	5	14	821	0.723	45.2							
	F6	1	5	7	5	7	641	0.610	38.1							
		2	4	8	4	9	444	0.507	31.7							
		3	4	5	4	4	460	0.556	34.7							
		4	5	3	5	0	564	0.573	35.8							
Chipped Ice On Island																
13 Feb 03		1	4	11	4	10	604	0.671	42.0	chipped						
		2	4	11	4	11	717	0.791	49.5	chipped						
		3	5	0	5	0	651	0.674	42.1	spray						

Sandwell

Date	Stake No.	top = 1		Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Stake	Salinity (ppt)	Daily Statistics		IVIK Overall Statistics	
		Length 1 (inch)	Length 1 (16ths)								Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)
		4	4	3	4	3	549	0.678	42.4	spray				
		1	5	9	5	9	920	0.856	53.5	chipped				
		2	4	0	3	15	568	0.741	46.3	chipped				
		3	4	5	4	5	600	0.720	45.0	spray				
		4	4	0	4	0	625	0.809	50.5	spray				
		5	5	4	5	4	641	0.632	39.5	spray				
		1	4	10	4	8	738	0.837	52.3	water				
		2	5	9	5	9	681	0.633	39.6	spray				
		3	5	10	5	10	673	0.619	38.7	spray				
		4	5	15	5	15	764	0.666	41.6	spray				
		5	4	2	4	1	426	0.538	33.7	spray				
		6	3	15	3	15	458	0.602	37.6	spray				
14 Feb 03	2	1	4	8	4	7	737	0.853	53.3	chipped				
		2	3	0	3	1	459	0.784	49.0	chipped				
		3	2	14	2	13	461	0.839	52.4	chipped				
	1	1	4	12	4	12	780	0.850	53.1	chipped				
		2	4	3	4	3	602	0.744	46.5	chipped				
		3	3	8	3	8	540	0.798	49.9	chipped				
17 Feb 03	2	1	4	12	4	11	783	0.859	53.7	chipped				
		2	5	13	5	10	789	0.714	44.6	chipped				
		3	4	11	4	11	713	0.787	49.2	chipped				
		4	3	14	3	14	529	0.706	44.1	chipped				
	1	1	4	1	4	2	645	0.815	51.0	chipped				
		2	4	15	4	14	769	0.811	50.7	chipped				
		3	4	5	4	4	698	0.844	52.7	chipped				

Sandwell

Date	Stake No.	top = 1		Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Stake	Salinity (ppt)	Daily Statistics		IVIK Overall Statistics		
		Length 1 (inch)	Length 1 (16ths)								Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)	
18 Feb 03	1	1	5	9	5	9	826	0.768	48.0	chipped					
		2	5	9	5	9	908	0.845	52.8	chipped					
		3	5	2	5	1	815	0.828	51.7	chipped					
		4	2	15	2	14	445	0.792	49.5	chipped					
	2	1	3	1	2	15	478	0.824	51.5	chipped					
		2	5	6	5	5	883	0.855	53.4	chipped					
		3	5	6	5	5	891	0.863	53.9	chipped					
	3	1	4	2	4	2	585	0.734	45.9	chipped					
		2	4	3	4	2	639	0.796	49.7	chipped					
		3	5	0	5	0	703	0.728	45.5	chipped					
	4	1	4	7	4	6	674	0.792	49.5	chipped					
		2	4	0	3	14	639	0.840	52.5	chipped					
		3	4	3	4	4	581	0.713	44.5	chipped					
		4	3	11	3	10	561	0.794	49.6	chipped					
									mean chipped	49.7					
									stdev	3.3					
								count	31						
								std error	0.6						



APPENDIX A5: OOGURUK ICE ISLAND DENSITY DATA

Date	Stake	top = 1 No.	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Stake	Salinity (ppt)	Daily Statistics		OOGURUK Overall Statistics			
												Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)		
3-Feb-03	H4	1	3	12	3	14	437	0.593	37.1			mean	38.0	22.7	mean	41.2	15.9
		2	5	12	5	13	678	0.607	37.9			min	32.2	22.0	stderr	0.5	2.2
	H4	1	4	6	4	3	569	0.688	43.0	H4	23.6	max	43.0	23.6	min	29.5	7.5
		2	4	15	4	15	492	0.516	32.2		22.5	stdev	4.0	0.8	max	55.5	23.6
		3	4	10	4	10	571	0.639	39.9		22.0	samples	5	3	stdev	5.9	6.2
												stderr	1.8	0.5	samples	134	8
												cores	2	1	cores	59	2
															days	14	
	5-Feb-03	H7	1	5	1	5	2	711	0.722	45.1	H7	15.5	mean	44.3	11.8		
			2	5	2	5	2	840	0.848	53.0		15.3	min	32.0	7.5		
3			5	1	5	1	810	0.828	51.7		11.1	max	53.0	15.5			
4			3	7	3	8	535	0.798	49.9		7.5	stdev	6.9	3.5			
5			3	14	3	14	621	0.829	51.8		9.7	samples	14	5			
H6		1	3	10	3	11	487	0.689	43.1			stderr	1.8	1.6			
		2	5	1	5	0	694	0.714	44.6			cores	3	1			
		3	4	0	3	12	409	0.546	34.1								
		4	4	11	4	11	479	0.529	33.0								
		5	4	14	4	15	486	0.513	32.0								
F6		1	4	15	4	14	714	0.753	47.1								
		2	5	2	5	2	693	0.700	43.7								
		3	4	11	4	12	634	0.695	43.5								
		4	5	4	5	3	767	0.760	47.5								
12-Feb-03	g5	1	4	15	4	15	573	0.600	37.5								
		2	4	12	4	14	542	0.583	36.4								
		3	3	14	3	13	354	0.477	29.8								
		4	4	0	4	1	390	0.501	31.3								

Sandwell

Date	Stake	top = 1 No.	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Stake	Salinity (ppt)	Daily Statistics		OOOGURUK Overall Statistics		
												Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)	
14-Feb-03	f6	1	3	0	3	4	316	0.523	32.7							
		2	5	0	4	15	453	0.472	29.5							
		3	3	6	3	4	326	0.509	31.8							
	f?	2	4	3	4	4	612	0.751	46.9							
	g5	1	2	11	2	13	439	0.826	51.6							
			2	3	2	3	6	508	0.809	50.6						
			3	5	0	5	2	771	0.788	49.3						
			4	4	13	4	12	598	0.647	40.4						
	g7	1	4	11	4	15	638	0.686	42.9							
			2	5	2	5	1	690	0.701	43.8						
			3	4	5	3	15	503	0.631	39.4						
	e7	1	4	13	4	15	597	0.634	39.6							
			2	4	13	4	14	584	0.624	39.0						
			3	2	13	2	12	377	0.701	43.8						
4			3	15	3	13	461	0.616	38.5							
5			4	0	4	2	483	0.615	38.5							
16-Feb-03	4	1	5	0	5	0	811	0.839	52.5							
		2	4	7	4	3	587	0.704	44.0							
		3	3	15	4	1	602	0.779	48.7							
		4	4	9	4	9	690	0.783	48.9							
		5	3	13	3	7	535	0.764	47.7							
3	1	4	1	4	0	604	0.775	48.5								

Sandwell

Date	Stake	top = 1 No.	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Stake	Salinity (ppt)	Daily Statistics		OOOGURUK Overall Statistics		
												Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)	
		2	4	15	4	14	606	0.639	39.9							
		3	4	0	4	4	512	0.642	40.1							
		4	4	13	4	11	565	0.615	38.5							
		5	3	13	3	14	463	0.623	39.0							
	2	1	4	8	4	8	635	0.730	45.6							
		2	5	1	5	0	682	0.701	43.8							
		3	3	1	2	15	379	0.654	40.9							
		4	3	10	3	12	481	0.675	42.2							
	1	1	3	13	3	14	552	0.743	46.4							
		2	4	14	4	14	613	0.651	40.7							
		3	4	14	4	15	526	0.555	34.7							
		4	4	13	4	11	563	0.613	38.3							
		5	4	14	4	5	492	0.554	34.6							
20-Feb-03	7e	1	3	6	3	11	562	0.824	51.5							
		2	2	13	2	12	420	0.781	48.8							
		3	2	7	2	7	362	0.768	48.0							
	7g	1	3	2	3	7	558	0.880	55.0							
		2	2	8	2	7	378	0.792	49.5							
		3	2	11	2	9	421	0.830	51.9							
		4	4	8	4	8	772	0.888	55.5							
23-Feb-03	70 31 56.7 150 10 40.0	1	4	8	4	9	556	0.635	39.7							
		2	4	6	4	5	525	0.625	39.1							
		3	4	4	4	4	479	0.583	36.4							
		4	3	11	3	12	418	0.582	36.4							
		5	3	15	4	0	446	0.581	36.3							

Sandwell

Date	Stake	top = 1 No.	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Stake	Salinity (ppt)	Daily Statistics		OOGURUK Overall Statistics	
												Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)
		6	3	9	3	9	386	0.561	35.0						
70 31 60.9 150 10 44.2		1	4	4	4	4	571	0.695	43.5						
		2	4	4	4	4	502	0.611	38.2						
		3	2	14	2	13	333	0.606	37.9						
		4	4	8	4	9	502	0.573	35.8						
		5	4	2	4	2	461	0.578	36.1						
		6	2	15	3	0	340	0.593	37.0						
		7	3	4	3	3	392	0.630	39.4						
70 31.601 150 10.356		1	3	8	3	10	396	0.575	35.9		reworked				
		2	4	3	4	3	481	0.594	37.1						
		3	4	3	4	3	596	0.736	46.0						
26-Feb-03	2	1	2	7	2	5	304	0.662	41.4		reworked				
		2	3	8	3	9	440	0.645	40.3						
		3	3	3	3	4	403	0.648	40.5						
		4	3	14	3	14	479	0.640	40.0						
		5	2	8	2	11	305	0.608	38.0						
		6	3	12	3	12	433	0.597	37.3						
		7	3	3	3	3	350	0.568	35.5						
		8	3	7	3	6	391	0.594	37.1						
		9	2	11	2	7	298	0.602	37.6						
	1	1	2	9	2	11	256	0.505	31.5						
		2	2	15	2	15	362	0.638	39.9						
		3	2	5	2	5	289	0.647	40.4						
		4	3	15	3	14	468	0.620	38.7						
		5	3	2	3	3	369	0.605	37.8						

Sandwell

Date	Stake	top = 1 No.	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Stake	Salinity (ppt)	Daily Statistics		OOGURUK Overall Statistics		
												Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)	
17-Mar-03	Depth(center of sample)		Length (mm)	Length (mm)	Dia (mm)	Volume (cc)	Weight (g)	Density (g/cc)	Density (lb/ft3)		Salinity ppt)					
0" to 37"	3	1	91	91.5	98	688.2971	597.3	0.86779	54.2							
	8	2	115.5	115.5	98	871.2144	710.1	0.81507	50.9							
	13	3	104	104	98	784.4701	601.7	0.76701	47.9							
	18	4	126	125.5	98	948.5299	677.5	0.71426	44.6							
	23	5	103.1	103.3	98	778.4357	525.4	0.67494	42.2							
	28	6	132.8	132.8	98	1001.708	590.1	0.58909	36.8							
	33	7	114.7	114.3	98	863.6714	505.1	0.58483	36.6							
38" to 49"	39	8	130	130	98	980.5876	671.5	0.68479	42.8							
	41	9	135.5	135.2	98	1020.943	585.8	0.57378	35.9							
	42	10	116	116	98	874.9859	487.9	0.55761	34.9							
	44	11	107	107	98	807.099	422.8	0.52385	32.7							
	45	12	112.2	112	98	845.5682	460	0.54401	34.0							
	47	13	116.3	116.3	98	877.2488	503.3	0.57373	35.9							
	48	14	93	94	98	705.2688	410	0.58134	36.3							
75.5" to 114"	76	15	117.4	117	98	884.0374	459.3	0.51955	32.5							
	81	16	93	91.8	98	696.9715	379.6	0.54464	34.0							
	86	17	79.8	79.8	98	601.9299	357.6	0.59409	37.1							
	92	18	93.5	93.5	98	705.2688	409.2	0.5802	36.3							
	97	19	85	85.8	98	644.1706	490	0.76067	47.5							
	102	20	130.4	129	97	958.4608	686.9	0.71667	44.8							
	107	21	113	113	98	852.3569	639.8	0.75062	46.9							
115" to 154"	112	22	92.2	92.7	98	697.3486	494.7	0.7094	44.3							
	117	23	120	120	97	886.7794	619.7	0.69882	43.7							
	122	24	100	99	97	735.2879	424.9	0.57787	36.1							
	127	25	90	90.5	97	666.932	382.6	0.57367	35.9							
	132	26	116.6	117	97	863.132	573.8	0.66479	41.5							
	137	27	76.3	77.5	97	568.2778	327.6	0.57648	36.0							

Sandwell

Date	Stake	top = 1 No.	Length 1 (inch)	Length 1 (16ths)	Length 2 (inch)	Length 2 (16ths)	Weight (g)	Density (g/cc)	Density (lb/cu.ft)	Stake	Salinity (ppt)	Daily Statistics		OOOGURUK Overall Statistics		
												Density (lb/cu.ft)	Salinity (ppt)	Density (lb/cu.ft)	Salinity (ppt)	
	142	28	87	87	97	642.9151	400.8	0.62341	39.0							
	147	29	102	102	98	769.3841	628.8	0.81728	51.1							
	152	30	99.7	99.4	98	750.9038	581.9	0.77493	48.4							
153" to 189"	155	31	110	110	97	812.8811	535.8	0.65914	41.2							
	162	32	106.3	107	97	788.1252	538.4	0.68314	42.7							
	168	33	126	126	97	931.1184	599.3	0.64363	40.2							
	175	34	143.3	143	97	1057.854	670.1	0.63345	39.6							
	181	35	99	98.3	97	729.0066	500.4	0.68641	42.9							
	188	36	60	61.8	97	450.0406	337	0.74882	46.8							
						Average		0.65527	41.0							
								0	41.0							
								200	41.0							



Appendix B1: Ice Motion Data for Ivik Sea Ice Monument

Ice Motion Data IVIK							Trend analysis		
Date	North	East	Delta N	Delta E	Delta r	Theta	days	days ^{0.5}	0.40 trend line
05 Feb	6037409.60	476477.58	0.00	0.00	0.00	#DIV/0!	0	0.00	0.00
07 Feb	6037409.29	476477.67	-0.31	0.09	0.32	-73.8	2	1.41	0.57
08 Feb	6037409.45	476477.53	-0.15	-0.05	0.16	-108.4	3	1.73	0.69
11 Feb	6037409.49	476477.61	-0.11	0.03	0.11	-74.7	6	2.45	0.98
12 Feb	6037409.72	476477.51	0.12	-0.07	0.14	120.3	7	2.65	1.06
17 Feb	6037410.82	476477.21	1.22	-0.37	1.27	106.9	12	3.46	1.39
20 Feb	6037410.91	476477.01	1.31	-0.57	1.43	113.5	15	3.87	1.55
21 Feb	6037411.16	476476.86	1.56	-0.72	1.72	114.8	16	4.00	1.60
22 Feb	6037411.06	476476.85	1.46	-0.73	1.63	116.6	17	4.12	1.65
23 Feb	6037411.10	476476.76	1.50	-0.82	1.71	118.7	18	4.24	1.70
24 Feb	6037411.18	476476.68	1.58	-0.90	1.82	119.7	19	4.36	1.74
26 Feb	6037411.16	476476.61	1.56	-0.97	1.84	121.9	21	4.58	1.83
28 Feb	6037411.11	476476.56	1.51	-1.02	1.82	124.0	23	4.80	1.92
01 Mar	6037411.18	476476.55	1.58	-1.03	1.89	123.1	24	4.90	1.96
02 Mar	6037411.17	476476.57	1.57	-1.01	1.87	122.8	25	5.00	2.00
03 Mar	6037411.17	476476.54	1.57	-1.04	1.88	123.5	26	5.10	2.04
04 Mar	6037411.13	476476.56	1.53	-1.02	1.84	123.7	27	5.20	2.08
06 Mar	6037411.17	476476.54	1.57	-1.04	1.88	123.5	29	5.39	2.15
10 Mar	6037411.27	476476.55	1.67	-1.03	1.96	121.7	33	5.74	2.30
11 Mar	6037411.29	476476.51	1.69	-1.07	2.00	122.3	34	5.83	2.33
12 Mar	6037411.20	476476.52	1.60	-1.06	1.92	123.5	35	5.92	2.37
13 Mar	6037411.23	476476.53	1.63	-1.05	1.94	122.8	36	6.00	2.40
14 Mar	6037411.38	476476.37	1.78	-1.21	2.15	124.2	37	6.08	2.43
15 Mar	6037411.42	476476.30	1.82	-1.28	2.23	125.1	38	6.16	2.47



Appendix B2: Ice Motion Data for Oooguruk Sea Ice Monument

Ice Motion Data	OOOGURUK						Trend analysis			
	Date	North	East	Delta N	Delta E	Delta r	Theta	days	days ^{0.5} trend line	0.13
	04 Feb	6040504.72	481867.39	0.00	0.00	0.00	#DIV/0!	0	0.00	0.00
	05 Feb	6040504.77	481867.21	0.05	-0.18	0.19	164.5	1	1.00	0.13
	07 Feb	6040504.70	481867.25	-0.02	-0.14	0.14	-171.9	3	1.73	0.23
	08 Feb	6040504.68	481867.30	-0.04	-0.09	0.10	-156.0	4	2.00	0.26
	11 Feb	6040504.77	481867.30	0.05	-0.09	0.10	150.9	7	2.65	0.34
	12 Feb	6040504.84	481867.46	0.12	0.07	0.14	59.7	8	2.83	0.37
	17 Feb	6040505.03	481867.63	0.31	0.24	0.39	52.3	13	3.61	0.47
	18 Feb	6040505.03	481867.66	0.31	0.27	0.41	48.9	14	3.74	0.49
	19 Feb	6040505.03	481867.71	0.31	0.32	0.45	44.1	15	3.87	0.50
	20 Feb	6040505.07	481867.63	0.35	0.24	0.42	55.6	16	4.00	0.52
	21 Feb	6040505.08	481867.74	0.36	0.35	0.50	45.8	17	4.12	0.54
	22 Feb	6040505.04	481867.83	0.32	0.44	0.55	36.4	18	4.24	0.55
	23 Feb	6040505.08	481867.83	0.36	0.44	0.57	39.3	19	4.36	0.57
	24 Feb	6040505.00	481867.96	0.28	0.57	0.64	26.2	20	4.47	0.58
	26 Feb	6040504.97	481867.99	0.25	0.60	0.65	22.6	22	4.69	0.61
	28 Feb	6040504.99	481867.95	0.27	0.56	0.62	25.3	24	4.90	0.64
	01 Mar	6040504.96	481867.89	0.24	0.50	0.55	25.6	25	5.00	0.65
	02 Mar	6040505.00	481867.88	0.28	0.49	0.56	29.7	26	5.10	0.66
	03 Mar	6040504.98	481867.82	0.26	0.43	0.50	31.2	27	5.20	0.68
	04 Mar	6040505.05	481867.77	0.33	0.38	0.50	41.0	28	5.29	0.69
	06 Mar	6040505.05	481867.85	0.33	0.46	0.57	35.7	30	5.48	0.71
	08 Mar	6040505.10	481867.84	0.38	0.45	0.59	40.2	32	5.66	0.74
	10 Mar	6040505.07	481867.83	0.35	0.44	0.56	38.2	34	5.83	0.76
	11 Mar	6040505.12	481867.77	0.40	0.38	0.55	46.5	35	5.92	0.77
	12 Mar	6040504.98	481867.93	0.26	0.54	0.60	25.7	36	6.00	0.78

Sandwell

Ice Motion Data

Trend analysis

Date	OOOGURUK						days	days ^{0.5}	trend line
	North	East	Delta N	Delta E	Delta r	Theta			
13 Mar	6040505.05	481868.11	0.33	0.72	0.79	24.6	37	6.08	0.79
14 Mar	6040505.05	481868.25	0.33	0.86	0.92	21.0	38	6.16	0.80
15 Mar	6040505.09	481868.34	0.37	0.95	1.02	21.3	39	6.24	0.81



Appendix B3: Ice Motion Data for Natchiq Sea Ice Monument

Ice Motion Data	NATCHIQ							Trend analysis		
	Date	North	East	Delta N	Delta E	Delta r	Theta	days	days ^{0.5}	0.03 trend line
	16 Feb	6025638.78	485609.11	0.00	0.00	0.00	#DIV/0!	0	0.00	0.00
	18 Feb	6025638.80	485609.11	0.02	0.00	0.02	90.0	2	1.41	0.04
	20 Feb	6025638.80	485609.14	0.02	0.03	0.04	33.7	4	2.00	0.06
	22 Feb	6025638.87	485609.06	0.09	-0.05	0.10	119.1	6	2.45	0.07
	23 Feb	6025638.85	485609.10	0.07	-0.01	0.07	98.1	7	2.65	0.08
	26 Feb	6025638.69	485609.07	-0.09	-0.04	0.10	-114.0	10	3.16	0.09
	01 Mar	6025638.56	485608.95	-0.22	-0.16	0.27	-126.0	13	3.61	0.11
	06 Mar	6025638.56	485608.82	-0.22	-0.29	0.36	-142.8	18	4.24	0.13
	10 Mar	6025638.54	485608.81	-0.24	-0.30	0.38	-141.0	22	4.69	0.14
	12 Mar	6025638.67	485608.94	-0.11	-0.17	0.20	-147.1	24	4.90	0.15
	13 Mar	6025638.65	485608.76	-0.13	-0.35	0.37	-159.6	25	5.00	0.15
	14 Mar	6025638.54	485608.60	-0.24	-0.51	0.56	-154.8	26	5.10	0.15
	15 Mar	6025638.36	485608.28	-0.42	-0.83	0.93	-153.2	27	5.20	0.16



Appendix C1: Sea Ice Flow Monitoring for Oooguruk

	OOOGURUK								
DATE	ICE MON #1								
	NORTH	EAST							
2.4.03	6040504.72	481867.39							
2.5.03	6040504.77	481867.21							
2.7.03	6040504.70	481867.25							
2.8.03	6040504.68	481867.30							
2.11.03	6040504.77	481867.30							
2.12.03	6040504.84	481867.46							
2.17.03	6040505.03	481867.63							
2.18.03	6040505.03	481867.66							
2.19.03	6040505.03	481867.71							
2.20.03	6040505.07	481867.63							
2.21.03	6040505.08	481867.74							
2.22.03	6040505.04	481867.83							
2.23.03	6040505.08	481867.83							
2.24.03	6040505.00	481867.96							
2.26.03	6040504.97	481867.99							
2.27.03	6040504.85	481867.95							
3.1.03	6040504.96	481867.89							
3.2.03	6040505.00	481867.88							
3.3.03	6040504.98	481867.82							
3.4.03	6040505.05	481867.77							
3.6.03	6040505.05	481867.85							
3.8.03	6040505.10	481867.84							
3.10.03	6040505.07	481867.83							

Sandwell

	OOOGURUK								
DATE	ICE MON #1								
	NORTH	EAST							
3.11.03	6040505.12	481867.77							
3.12.03	6040504.98	481867.93							
3.13.03	6040505.05	481868.11							
3.14.03	6040505.05	481868.25							
3.15.03	6040505.09	481868.34							
3.16.03	6040505.07	481868.53							
3.17.03	6040505.07	481868.44							
3.18.03	6040505.11	481868.38							
3.19.03	6040505.04	481868.44							
3.20.03	6040505.04	481868.51							
3.22.03	6040505.06	481868.61							
3.24.03	6040505.09	481868.68							
3.27.03	6040505.19	481868.82							
3.29.03	6040505.12	481868.84							
3.31.03	6040505.13	481868.76							
4.2.03	6040505.10	481868.73							
4.5.03	6040505.17	481868.71							
4.8.03	6040505.18	481868.66							
4.10.03	6040505.18	481868.68	Final Monitoring Date 4/10/03						
LAST MOVE	E	0.02							
TOTAL MOVE	ENE	1.37							



Appendix C2: Sea Ice Flow Monitoring for Ivik Ice Island

	IVIK								
DATE	ICE MON #2								
	NORTH	EAST							
2.5.03	6037409.60	476477.58							
2.7.03	6037409.29	476477.67							
2.8.03	6037409.45	476477.53							
2.11.03	6037409.49	476477.61							
2.12.03	6037409.72	476477.51							
2.17.03	6037410.82	476477.21							
2.20.03	6037410.91	476477.01							
2.21.03	6037411.16	476476.86							
2.22.03	6037411.06	476476.85							
2.23.03	6037411.10	476476.76							
2.24.03	6037411.18	476476.68							
2.26.03	6037411.16	476476.61							
2.28.03	6037411.11	476476.56							
3.1.03	6037411.18	476476.55							
3.2.03	6037411.17	476476.57							
3.3.03	6037411.17	476476.54							
3.4.03	6037411.13	476476.56							
3.6.03	6037411.17	476476.54							
3.10.03	6037411.27	476476.55							
3.11.03	6037411.29	476476.51							
3.12.03	6037411.20	476476.52							
3.13.03	6037411.23	476476.53							
3.14.03	6037411.38	476476.37							

Sandwell

	IVIK								
DATE	ICE MON #2								
	NORTH	EAST							
3.15.03	6037411.42	476476.30							
3.17.03	6037411.48	476476.24							
3.18.03	6037411.44	476476.17							
3.19.03	6037411.44	476476.15							
3.20.03	6037411.48	476476.01							
3.22.03	6037411.64	476475.90							
3.24.03	6037411.69	476475.92							
3.27.03	6037411.85	476475.55							
3.29.03	6037411.95	476475.36							
3.31.03	6037411.91	476475.48							
4.2.03	6037411.97	476475.57							
4.5.03	6037412.00	476475.49							
4.8.03	6037411.95	476475.50							
4.10.03	6037411.95	476475.54	Final Monitoring Date 4/10/03						
LAST MOVE	E	0.04							
TOTAL MOVE	NW	3.11							



C3: Sea Ice Flow Monitoring for Natchiq

	NATCHIQ								
DATE	ICE MON #3A								
	NORTH	EAST							
2.16.03	6025638.78	485609.11							
2.18.03	6025638.80	485609.11							
2.20.03	6025638.80	485609.14							
2.22.03	6025638.87	485609.06							
2.23.03	6025638.85	485609.10							
2.26.03	6025638.69	485609.07							
3.1.03	6025638.56	485608.95							
3.6.03	6025638.56	485608.82							
3.10.03	6025638.54	485608.81							
3.12.03	6025638.67	485608.94							
3.13.03	6025638.65	485608.76							
3.14.03	6025638.54	485608.60							
3.15.03	6025638.36	485608.28							
3.16.03	6025638.51	485608.33							
3.17.03	6025638.38	485608.10							
3.18.03	6025638.46	485608.25							
3.19.03	6025638.48	485608.25							
3.20.03	6025638.61	485608.19							
3.22.03	6025638.47	485608.23							
3.24.03	6025638.49	485608.18							
3.27.03	6025638.48	485607.81							
3.29.03	6025638.47	485607.90							
3.31.03	6025638.38	485607.85							

Sandwell

	NATCHIQ								
DATE	ICE MON #3A								
	NORTH	EAST							
4.2.03	6025638.29	485607.75							
4.5.03	6025638.41	485607.87							
4.10.03	6025638.35	485607.87	Final Monitoring Date 4/10/03						
LAST MOVE	S	0.06							
TOTAL MOVE	WSW	1.31							

APPENDIX D1: ICE PAD STABILITY FOR IVIK

Ivik Pad Motion 4

DATE	IVIK			MOVE FROM LAST			TOTAL MOVEMENT		
	PAD MON 4								
	NORTH	EAST	ELEV.	d N	d E	d Elev	d N	d E	d Elev
2003.02.20	6,034,850.80	477,060.23	19.27						
2002.02.21	6,034,850.82	477,060.24	19.00	0.02	0.01	-0.27			
2003.02.22	6,034,850.77	477,060.24	19.01	-0.05	0.00	0.01	-0.03	0.01	-0.26
2003.02.23	6,034,850.82	477,060.22	19.05	0.05	-0.02	0.04	0.02	-0.01	-0.22
2003.02.24	6,034,850.74	477,060.23	18.84	-0.08	0.01	-0.21	-0.06	0.00	-0.43
2003.02.26	6,034,850.76	477,060.24	18.85	0.02	0.01	0.01	-0.04	0.01	-0.42
2003.02.28	6,034,850.72	477,060.28	18.84	-0.04	0.04	-0.01	-0.08	0.05	-0.43
2003.03.01	6,034,850.68	477,060.20	18.47	-0.04	-0.08	-0.37	-0.12	-0.03	-0.80
2003.03.02	6,034,850.76	477,060.22	18.73	0.08	0.02	0.26	-0.04	-0.01	-0.54
2003.03.03	6,034,850.77	477,060.20	18.78	0.01	-0.02	0.05	-0.03	-0.03	-0.49
2003.03.04	6,034,850.84	477,060.27	19.20	0.07	0.07	0.42	0.04	0.04	-0.07
2003.03.06	6,034,850.85	477,060.29	18.85	0.01	0.02	-0.35	0.05	0.06	-0.42
2003.03.10	6,034,850.77	477,060.23	18.67	-0.08	-0.06	-0.18	-0.03	0.00	-0.60
2003.03.11	6,034,850.84	477,060.17	18.61	0.07	-0.06	-0.06	0.04	-0.06	-0.66
2003.03.12	6,034,850.72	477,060.24	18.56	-0.12	0.07	-0.05	-0.08	0.01	-0.71
2003.03.13	6,034,850.78	477,060.23	18.54	0.06	-0.01	-0.02	-0.02	0.00	-0.73
2003.03.14	6,034,850.77	477,060.19	18.56	-0.01	-0.04	0.02	-0.03	-0.04	-0.71

DATE	IVIK			MOVE FROM LAST			TOTAL MOVEMENT		
	PAD MON 4								
	NORTH	EAST	ELEV.	d N	d E	d Elev	d N	d E	d Elev
2003.03.15	6,034,850.79	477,060.17	18.64	0.02	-0.02	0.08	-0.01	-0.06	-0.63
2003.03.17	6,034,850.73	477,060.19	18.60	-0.06	0.02	-0.04	-0.07	-0.04	-0.67
2003.03.18	6,034,850.78	477,060.22	18.68	0.05	0.03	0.08	-0.02	-0.01	-0.59
2003.03.19	6,034,850.81	477,060.23	18.64	0.03	0.01	-0.04	0.01	0.00	-0.63
2003.03.20	6,034,850.70	477,060.15	18.79	-0.11	-0.08	0.15	-0.10	-0.08	-0.48
2003.03.22	6,034,850.71	477,060.22	18.32	0.01	0.07	-0.47	-0.09	-0.01	-0.95
2003.03.24	6,034,850.74	477,060.18	18.52	0.03	-0.03	0.20	-0.06	-0.05	-0.75
2003.03.27	6,034,850.76	477,060.15	18.46	0.02	-0.04	-0.06	-0.04	-0.08	-0.81
2003.03.29	6,034,850.67	477,060.12	18.67	-0.09	-0.03	0.21	-0.13	-0.11	-0.60
2003.03.31	6,034,850.64	477,060.20	18.34	-0.03	0.08	-0.33	-0.16	-0.03	-0.93
2003.04.02	6,034,850.84	477,059.98	18.54	0.20	-0.22	0.20	0.04	-0.25	-0.73
2003.04.05	6,034,850.67	477,060.15	18.24	-0.17	0.17	-0.30	-0.13	-0.08	-1.03
2003.04.08	6,034,850.74	477,060.13	18.43	0.07	-0.02	0.19	-0.06	-0.10	-0.84
2003.04.10	6,034,850.70	477,060.14	18.34	-0.04	0.01	-0.09	-0.10	-0.09	-0.93
Final Monitoring Date 4/10/03									



Ivik Pad Motion 5

DATE	IVIK			MOVE FROM LAST	d N	d E	d Elev	TOTAL MOVEMENT					
	PAD MON 5							d N	d E	d Elev	d N	d E	d Elev
	NORTH	EAST	ELEV.										
2003.02.20	6,035,097.95	476,791.93	18.26										
2002.02.21	6,035,097.91	476,791.93	17.99	-0.04	0.00	-0.27							
2003.02.22	6,035,097.84	476,791.91	18.12	-0.07	-0.02	0.13	-0.11	-0.02	-0.14				
2003.02.23	6,035,097.92	476,791.93	18.22	0.08	0.02	0.10	-0.03	0.00	-0.04				
2003.02.24	6,035,097.87	476,791.95	18.02	-0.05	0.02	-0.20	-0.08	0.02	-0.24				
2003.02.26	6,035,097.86	476,791.94	18.06	-0.01	-0.01	0.04	-0.09	0.01	-0.20				
2003.02.28	6,035,097.78	476,791.93	18.12	-0.08	-0.01	0.06	-0.17	0.00	-0.14				
2003.03.01	6,035,097.82	476,791.95	17.68	0.04	0.02	-0.44	-0.13	0.02	-0.58				
2003.03.02	6,035,097.85	476,791.92	17.94	0.03	-0.03	0.26	-0.10	-0.01	-0.32				
2003.03.03	6,035,097.87	476,791.90	17.87	0.02	-0.02	-0.07	-0.08	-0.03	-0.39				
2003.03.04	6,035,097.88	476,791.99	17.86	0.01	0.09	-0.01	-0.07	0.06	-0.40				
2003.03.06	6,035,097.96	476,791.95	17.85	0.08	-0.04	-0.01	0.01	0.02	-0.41				
2003.03.10	6,035,097.96	476,789.81	17.73	0.00	-2.14	-0.12	0.01	-2.12	-0.53				
2003.03.11	6,035,097.90	476,791.89	17.62	-0.06	2.08	-0.11	-0.05	-0.04	-0.64				
2003.03.12	6,035,097.89	476,791.95	17.55	-0.01	0.06	-0.07	-0.06	0.02	-0.71				
2003.03.13	6,035,097.88	476,791.92	17.72	-0.01	-0.03	0.17	-0.07	-0.01	-0.54				
2003.03.14	6,035,097.86	476,791.89	17.67	-0.02	-0.03	-0.05	-0.09	-0.04	-0.59				
2003.03.15	6,035,097.89	476,791.90	17.83	0.03	0.01	0.16	-0.06	-0.03	-0.43				
2003.03.17	6,035,097.84	476,791.89	17.62	-0.05	-0.01	-0.21	-0.11	-0.04	-0.64				

DATE	IVIK			MOVE FROM LAST	d N	d E	d Elev	TOTAL MOVEMENT					
	PAD MON 5							d N	d E	d Elev	d N	d E	d Elev
	NORTH	EAST	ELEV.										
2003.03.18	6,035,097.84	476,791.92	17.82		0.00	0.03	0.20	-0.11	-0.01	-0.44			
2003.03.19	6,035,097.86	476,791.95	17.89		0.02	0.03	0.07	-0.09	0.02	-0.37			
2003.03.20	6,035,097.73	476,791.87	17.63		-0.13	-0.08	-0.26	-0.22	-0.06	-0.63			
2003.03.22	6,035,097.78	476,791.94	17.67		0.05	0.07	0.04	-0.17	0.01	-0.59			
2003.03.24	6,035,097.77	476,791.97	17.65		-0.01	0.02	-0.02	-0.18	0.04	-0.61			
2003.03.27	6,035,097.77	476,791.96	17.62		0.00	0.00	-0.03	-0.18	0.03	-0.64			
2003.03.29	6,035,097.76	476,791.80	17.69		-0.01	-0.16	0.07	-0.19	-0.13	-0.57			
2003.03.31	6,035,097.87	476,791.88	18.19		0.11	0.08	0.50	-0.08	-0.05	-0.07			
2003.04.02	6,035,097.82	476,791.84	17.46		-0.05	-0.04	-0.73	-0.13	-0.09	-0.80			
2003.04.05	6,035,097.69	476,791.98	17.52		-0.13	0.14	0.06	-0.26	0.05	-0.74			
2003.04.08	6,035,097.85	476,791.90	17.65		0.16	-0.08	0.13	-0.10	-0.03	-0.61			
2003.04.10	6,035,097.74	476,791.96	17.53		-0.11	0.06	-0.12	-0.21	0.03	-0.73			
Final Monitoring Date 4/10/03													

Appendix D2: Ice Pad Stability Survey for Oooguruk

Oooguruk Pad Motion 9

OOOGURUK									
PAD MON 9				MOVE FROM LAST			TOTAL MOVE		
DATE	NORTH	EAST	ELEV.	d N	d E	d Elev	d N	d E	d Elev
3/10/2003	6,042,289.33	479,674.83	18.87						
3/11/2003	6,042,289.44	479,674.83	18.81	0.11	0.00	-0.06			
3/12/2003	6,042,289.36	479,674.85	18.61	-0.08	0.02	-0.20	0.03	0.02	-0.26
3/13/2003	6,042,289.40	479,674.87	18.63	0.04	0.02	0.02	0.07	0.04	-0.24
3/14/2003	6,042,289.38	479,674.87	18.59	-0.02	0.00	-0.04	0.05	0.04	-0.28
3/15/2003	6,042,289.38	479,674.89	18.55	0.00	0.02	-0.04	0.05	0.06	-0.32
3/16/2003	6,042,289.48	479,674.93	18.57	0.10	0.04	0.02	0.15	0.10	-0.30
3/17/2003	6,042,289.37	479,674.89	18.49	-0.11	-0.04	-0.08	0.04	0.06	-0.38
3/18/2003	6,042,289.35	479,674.90	18.46	-0.02	0.01	-0.03	0.02	0.07	-0.41
3/19/2003	6,042,289.35	479,674.95	18.43	0.00	0.05	-0.03	0.02	0.12	-0.44
2003.03.20	6,042,289.04	479,674.65	18.71	-0.31	-0.30	0.28	-0.29	-0.18	-0.16
2003.03.22	6,042,288.99	479,674.67	18.63	-0.05	0.02	-0.08	-0.34	-0.16	-0.24
2003.03.24	6,042,289.33	479,674.95	18.24	0.34	0.28	-0.39	0.00	0.12	-0.63
2003.03.27	6,042,289.35	479,674.96	18.16	0.02	0.00	-0.08	0.02	0.12	-0.71
2003.03.29	6,042,289.37	479,674.97	18.26	0.02	0.01	0.10	0.04	0.14	-0.61
2003.03.31	6,042,289.24	479,674.91	18.10	-0.13	-0.06	-0.16	-0.09	0.08	-0.77
2003.04.02	6,042,289.42	479,674.88	18.33	0.18	-0.03	0.23	0.09	0.05	-0.54
Final Monitoring Date 4/2/03									

Sandwell

	OOOGURUK								
	PAD MON 9			MOVE FROM LAST			TOTAL MOVE		
DATE	NORTH	EAST	ELEV.	d N	d E	d Elev	d N	d E	d Elev



Oooguruk Pad Motion 10

DATE	OOOGURUK			MOVE FROM LAST			TOTAL MOVE		
	PAD MON 10			d N	d E	d Elev	d N	d E	d Elev
	NORTH	EAST	ELEV.						
3/10/2003	6,042,628.88	479,526.04	20.8						
3/11/2003	6,042,628.90	479,526.08	20.70	0.02	0.04	-0.08			
3/12/2003	6,042,628.88	479,526.01	20.7	-0.02	-0.07	-0.03	0.00	-0.03	-0.11
3/13/2003	6,042,628.94	479,526.12	20.7	0.06	0.11	-0.02	0.06	0.08	-0.13
3/14/2003	6,042,628.89	479,526.06	20.6	-0.05	-0.06	-0.02	0.01	0.02	-0.15
3/15/2003	6,042,628.86	479,526.05	20.6	-0.03	-0.01	0.00	-0.02	0.01	-0.15
3/16/2003	6,042,628.98	479,526.13	20.6	0.12	0.08	0.01	0.10	0.09	-0.14
3/17/2003	6,042,628.94	479,526.06	20.5	-0.04	-0.07	-0.13	0.06	0.02	-0.27
3/18/2003	6,042,628.93	479,526.13	20.5	-0.01	0.07	-0.02	0.05	0.09	-0.29
3/19/2003	6,042,628.94	479,526.09	20.5	0.01	-0.04	0.00	0.06	0.05	-0.29
2003.03.20	6,042,628.67	479,525.81	21	-0.27	-0.28	0.48	-0.21	-0.23	0.19
2003.03.22	6,042,628.59	479,525.91	20.5	-0.08	0.10	-0.46	-0.29	-0.13	-0.27
2003.03.24	6,042,628.89	479,526.09	20.3	0.30	0.18	-0.19	0.01	0.05	-0.46
2003.03.27	6,042,628.94	479,526.10	20.1	0.06	0.01	-0.18	0.06	0.06	-0.64
2003.03.29	6,042,628.94	479,526.05	20.1	0.00	-0.05	-0.09	0.06	0.01	-0.73
2003.03.31	6,042,628.90	479,526.07	20.2	-0.04	0.02	0.18	0.02	0.03	-0.55
2003.04.02	6,042,628.97	479,526.07	20.30	0.07	0.00	0.07	0.09	0.03	-0.48
Final Monitoring Date 4/2/03									



Appendix D3: Ice Pad Stability Survey Natchiq

Natchiq Pad Motion 6

DATE	NATCHIQ			MOVE FROM LAST	d N	d E	d Elev	TOTAL MOVEMENT		
	PAD MON 6	NORTH	EAST					ELEV.	d N	d E
2003.03.09	6,023,878.52	487,595.84	20.55							
2003.03.10	6,023,878.41	487,595.83	20.35	-0.11	-0.01	-0.20				
2003.03.12	6,023,878.42	487,595.77	20.33	0.01	-0.06	-0.02	-0.10	-0.07	-0.22	
2003.03.13	6,023,878.39	487,595.80	20.29	-0.03	0.03	-0.04	-0.13	-0.04	-0.26	
2003.03.15	6,023,878.42	487,595.73	20.23	0.03	-0.07	-0.06	-0.10	-0.11	-0.32	
2003.03.17	6,023,878.35	487,595.64	N/A	-0.07	-0.09	N/A	-0.17	-0.20	N/A	
2003.03.18	6,023,878.36	487,595.73	20.18	0.01	0.09	-0.05	-0.16	-0.11	-0.37	
2003.03.19	6,023,878.37	487,595.72	20.26	0.01	-0.01	0.08	-0.15	-0.12	-0.29	
2003.03.20	6,023,878.35	487,595.69	20.45	-0.02	-0.03	0.19	-0.17	-0.15	-0.10	
2003.03.22	6,023,878.38	487,595.77	20.04	0.03	0.08	-0.41	-0.14	-0.07	-0.51	
2003.03.24	6,023,878.40	487,595.78	20.15	0.02	0.01	0.11	-0.12	-0.06	-0.40	
2003.03.27	6,023,878.44	487,595.82	19.73	0.04	0.04	-0.42	-0.08	-0.02	-0.82	
2003.03.29	6,023,878.49	487,595.77	20.15	0.05	-0.05	0.42	-0.03	-0.07	-0.40	
2003.03.31	6,023,878.36	487,595.70	19.87	-0.13	-0.07	-0.28	-0.16	-0.14	-0.68	
2003.04.02	6023878.609	487596.07	20.34	0.25	0.37	0.47	0.09	0.23	-0.21	



Natchiq Pad Motion 7


DATE	NATCHIQ			MOVE FROM LAST	d N	d E	d Elev	TOTAL MOVEMENT		
	PAD MON 7	NORTH	EAST					ELEV.	d N	d E
2003.03.09	6,023,474.74	487,371.97	22.43							
2003.03.10	6,023,474.56	487,371.98	22.20	-0.18	0.01	-0.23				
2003.03.12	6,023,474.50	487,371.84	22.51	-0.06	-0.14	0.31	-0.24	-0.13	0.08	
2003.03.13	6,023,474.66	487,371.98	22.32	0.16	0.14	-0.19	-0.08	0.01	-0.11	
2003.03.15	6,023,474.65	487,371.89	22.24	-0.01	-0.09	-0.08	-0.09	-0.08	-0.19	
2003.03.17	6,023,474.56	487,371.75	N/A	-0.09	-0.14	N/A	-0.18	-0.22	N/A	
2003.03.18	6,023,474.55	487,371.87	22.32	-0.01	0.12	0.08	-0.19	-0.10	-0.11	
2003.03.19	6,023,474.56	487,371.84	22.45	0.01	-0.03	0.13	-0.18	-0.13	0.02	
2003.03.20	6,023,474.53	487,371.78	22.23	-0.03	-0.06	-0.22	-0.21	-0.19	-0.20	
2003.03.22	6,023,474.67	487,371.94	22.29	0.14	0.16	0.06	-0.07	-0.03	-0.14	
2003.03.24	6,023,474.65	487,371.92	22.35	-0.02	-0.01	0.06	-0.09	-0.05	-0.08	
2003.03.27	6,023,474.62	487,371.93	22.25	-0.03	0.01	-0.10	-0.12	-0.04	-0.18	
2003.03.29	6,023,474.58	487,372.01	22.14	-0.04	0.08	-0.11	-0.16	0.04	-0.29	
2003.03.31	6,023,474.48	487,372.06	22.15	-0.10	0.05	0.01	-0.26	0.09	-0.28	
2003.04.02	6023474.506	487371.91	22.14	0.03	-0.15	-0.01	-0.23	-0.06	-0.29	





Natchiq Pad Motion 8


DATE	NATCHIQ			MOVE THIS SURVEY			TOTAL MOVEMENT		
	PAD MON 8	EAST	ELEV.	d N	d E	d Elev	d N	d E	d Elev
2003.03.09	6,023,223.37	487,610.46	23.37						
2003.03.10	6,023,223.33	487,610.45	23.16	-0.04	-0.01	-0.21			
2003.03.13	6,023,223.44	487610.57	23.25	0.11	0.12	0.09	0.07	0.11	-0.12
2003.03.15	6,023,223.36	487,610.37	23.53	-0.08	-0.20	0.28	-0.01	-0.09	0.16
2003.03.17	6,023,223.31	487,610.35	N/A	-0.05	-0.02	N/A	-0.06	-0.11	N/A
2003.03.18	6,023,223.27	487,610.45	23.16	-0.04	0.10	-0.37	-0.10	-0.01	-0.21
2003.03.19	6,023,223.24	487,610.43	23.39	-0.03	-0.02	0.23	-0.13	-0.03	0.02
2003.03.20	6,023,223.33	487,610.39	23.40	0.09	-0.04	0.01	-0.04	-0.07	0.03
2003.03.22	6,023,223.36	487,610.47	23.16	0.03	0.08	-0.24	-0.01	0.01	-0.21
2003.03.24	6,023,223.37	487,610.42	23.23	0.01	-0.05	0.07	0.00	-0.04	-0.14
2003.03.27	6,023,223.36	487,610.49	23.14	-0.01	0.07	-0.09	-0.01	0.03	-0.23
2003.03.29	6,023,223.33	487,610.45	23.37	-0.03	-0.04	0.23	-0.04	-0.01	0.00
2003.03.31	6,023,223.30	487,610.44	23.20	-0.03	-0.01	-0.17	-0.07	-0.02	-0.17
2003.04.02	6023223.35	487610.29	23.29	0.05	-0.15	0.09	-0.02	-0.17	-0.08


Appendix D4 : Island and Road Temperatures











THREE WELLS FROM THREE ICE ISLANDS

Harrison Bay, Alaska
December 2002 – April 2003
Pioneer Natural Resources
Sandwell Engineering Inc.

By

D. M. Masterson

P. A. Spencer

W. P. Graham

OVERVIEW

- ❑ Location in Harrison Bay Alaska, Prudhoe Bay
- ❑ 20 miles of grounded ice road constructed
- ❑ 3 ice islands constructed from sprayed and chipped ice
- ❑ 3 well successfully drilled on IVIK, NATCHIQ & OOOGURUK
- ❑ 2 Rigs 27E and NORDIC 3


PARTICIPANTS

- ❑ CLIENT : PIONEER DRILLING
- ❑ DESIGN & QC: SANDWELL ENGINEERING
- ❑ PROJECT MANAGEMENT : NATCHIQ
- ❑ CONSTRUCTION : AIC, PEAK, CATCO
- ❑ SURVEYING : LOUNDSBURY & Associates
- ❑ NABORS RIG 27E
- ❑ NORDIC RIG 3

PROJECT MILESTONES

- ❑ ISLAND DESIGN : Late December 2002
- ❑ START OF FIELD WORK : Early January 2003
- ❑ DRILL RIG 27E ON IVIK : 19 February 2003
- ❑ DRILL RIG 27E OOOGURUK : 14 March 2003
- ❑ DRILL RIG NORDIC 3 ON NATCHIQ : 16 March 2003
- ❑ EQUIPMENT OFF ICE : 03 April 2003
- ❑ APPROXIMATE CONSTRUCTION COST \$14,000,000

PROJECT MAP



PROJECT SCHEDULE

ID	Task Name	Duration	Start	Finish	January							February				March				April			
					12/22	12/29	1/5	1/12	1/19	1/26	2/2	2/9	2/16	2/23	3/2	3/9	3/16	3/23	3/30	4/6	4/13	4/20	
1	Engineering	20 days?	Mon 12/30/02	Fri 1/24/03																			
2																							
3	Ivik Site Prep	4 edays?	Wed 1/15/03	Sun 1/19/03																			
4	Build ice road to Ivik	30 edays?	Mon 1/13/03	Wed 2/12/03																			
5	Mob pumps to Ivik	1 eday	Thu 1/23/03	Fri 1/24/03																			
6	Spray Ivik Island	25 edays?	Fri 1/24/03	Tue 2/18/03																			
7	Prepare Isl - Cellar etc.	5 edays?	Tue 2/18/03	Sun 2/23/03																			
8	Rig up and drill well-test-log	15 edays?	Sun 2/23/03	Mon 3/10/03																			
9																							
10	Natchiq site prep	4 edays?	Wed 1/22/03	Sun 1/26/03																			
11	Mob pumps to Natchiq	1 eday?	Tue 2/4/03	Wed 2/5/03																			
12	Spray Natchiq	25 edays?	Wed 2/5/03	Sun 3/2/03																			
13	Prepare Isl - Cellar etc.	5 edays?	Sun 3/2/03	Fri 3/7/03																			
14	Rig up and drill well-test-log	15 edays?	Mon 3/10/03	Tue 3/25/03																			
15																							
16	Oooguruk site prep	4 edays?	Wed 1/22/03	Sun 1/26/03																			
17		1 eday?	Thu 1/23/03	Fri 1/24/03																			
18	Spray Oooguruk	25 edays?	Fri 1/24/03	Tue 2/18/03																			
19	Finish ice road	10 days?	Wed 2/12/03	Tue 2/25/03																			
20	Prepare Isl - Cellar etc.	5 edays?	Tue 2/18/03	Sun 2/23/03																			
21	Rig up and drill well-test-log	15 edays?	Sun 2/23/03	Mon 3/10/03																			

ISLAND DESIGN


PIONEER NATURAL RESOURCES

Sandwell

WATER DEPTH

LOCATION	CHART DEPTH	DESIGN DEPTH
Natchiq	7.5 ft.	9.5 ft.
Ivik	10 ft.	12 ft.
Oooguruk	12 ft.	14 ft.

ISLAND CROSS SECTION




ISLAND PARAMETERS

- ❑ Island Working Surface Diameter : 600 ft
- ❑ Island Volume : 325,000 yd³ to 360,000 yd³
- ❑ Spray ice minimum density : 39 lb/ft³
- ❑ Design Level Ice Thickness : 5.0ft
- ❑ Storm Surge allowance : 2.0 ft



IVIK ISLAND GEOMETRY

NOTES:



1. OF THE ISLAND, ALL PERMANENT STRUCTURES AND FUEL STORAGE ON THE ISLAND SHALL BE SET BACK A DISTANCE OF AT LEAST 50 FEET FROM THE EDGE OF THE WORKING SURFACE. CONSUMABLE STORAGE OF TUBULARS AND DRY MUD PRODUCTS IS ALLOWED WITHIN THIS BUFFER ZONE.
2. ALL DIMENSIONS SHOWN ARE FEET UNLESS OTHERWISE NOTED.




PLAN



SECTION A-A



LOCATION OF BUILD-UP STAKES



RAMPS ONTO ISLAND SECTION -B

DWG. No.	REFERENCE	REV.	DWG. No.	REFERENCE	REV.	DATE	REVISION	APPROVED BY	DATE	REVISION	APP'D	DATE	PRELIMINARY ISSUE	NO.

APPROVED	DATE	SCALE	300 FT DIA. WORKING SURFACE
DRAWN	DATE	SCALE	300 FT CORE DIAMETER
CHECKED	DATE	SCALE	IVIK - THETIS IS. ICE ISLAND
DESIGNED	DATE	SCALE	PIONEER NAT. RES.
PROJECT	DATE	SCALE	DWG. 242013 C 002 [REV]



THIS DRAWING AND THE CONTENTS ARE CONFIDENTIAL FOR THE PRIVATE REQUISITION OF THE CLIENT AND FOR USE ONLY FOR THE PROJECT FOR WHICH IT WAS PREPARED.

ROAD CONSTRUCTION

PIONEER NATURAL RESOURCES

Sandwell

FROM OLIKTOK POINT ONTO SEA ICE



CATCO FLOODER



THICKENING ICE



FLOODED ROAD



ICE CHIPPER (1)



ICE CHIPPER (2)



CHIPPED ICE DETAIL



LOADING CHIPS



DUMPING, GRADING, WATERING CHIPS



DUMPING CHIPS on IVIK RAMP



CRACKS NEXT TO GROUNDED ROAD to IVIK



PROFILING ROAD with hot water THERMO-DRILL



ISLAND CONSTRUCTION

PIONEER NATURAL RESOURCES

Sandwell

CONSTRUCTION MONITORING

Item	Number of sites	Frequency
Constructed Volume/Shape	Build-up stakes	Every day
Ice Temperature	1 Vertical profile	Every day
Density/Salinity	1 Core	Every other day
Pump operation parameters	All pumps	Every Day

ROLLIGON 3000 gpm Spray Unit



5000 gpm CATCO PUMP



AIC 3500 gpm PUMP (1)



AIC 3500 gpm PUMP (2)



OOOGURUK CONSTRUCTION (1)



SAMPLE CORING on IVIK (1)



SAMPLE CORING on IVIK (2)




SAMPLE ICE CORES



SPRAY ICE DENSITY

SPRAY ICE DENSITY FROM IVIK, OOGURUK, NATCHIQ



GRADING OOOGURUK (1)



GRADING OOOGURUK (2)



OOOGURUK CONSTRUCTION (2)




NATCHIQ (1)



ISLAND BUILD-UPS

ISLAND MEAN ELEVATION : SURVEY DATA



DRILLING

PIONEER NATURAL RESOURCES

Sandwell

RIG 27E Ready to move



VECO on NATCHIQ



IVIK CELLAR




RIG 27E on IVIK



IVIK March 16



NORDIC 3 Moving (1)



NORDIC 3 Moving (2)



NORDIC 3 ROAD DAMAGE (1)



NORDIC 3 ROAD DAMAGE (2)



OTHER EQUIPMENT

CATCO LATV



CATCO RD85



WATER TRUCK



LUNCHTIME AIC TRUCKS



LUNCHTIME PEAK TRUCKS



GOOD DAY FOR A DRIVE




ISLAND PERFORMANCE

PIONEER NATURAL RESOURCES


Sandwell

ISLAND SETTLEMENT

IVIK ELEVATION SURVEY




ICE TEMPERATURES




SEA ICE MOVEMENT

NET MOVEMENT VECTORS




AIR TEMPERATURE

NOAA/NOS/CO-OPS
Air Temperature Plot
9497645 Prudhoe Bay , AK
from 01/01/2003 - 04/30/2003




BAROMETRIC PRESSURE

NOAA/NOS/CO-OPS
Barometric Pressure Plot
9497645 Prudhoe Bay , AK
from 01/01/2003 - 04/30/2003



WIND SPEED & DIRECTION

NOAA/NOS/CO-OPS
Wind Speed/Dir
9497645 Prudhoe Bay, AK
from 01/01/2003 - 04/30/2003



SANDWELL FIELD TEAM

- Dan Masterson
- Paul Spencer
- Bill Graham
- Jim Singletary